

Office (763) 862-8000 Fax (763) 862-8042

June 17, 2021

Honorable Mayor and Councilmembers City of Ham Lake 15544 Central Avenue NE Ham Lake, Minnesota 55304

Re: Tippecanoe Street Feasibility Report

Dear Mayor and City Council Members,

The City Council directed the preparation of this report on May 3, 2021. The purpose is to determine the project necessity, feasibility, cost effectiveness and recommendations for the re-alignment and reconstruction of Tippecanoe Street from Constance Boulevard south to the cul-de-sac. The proposed improvements are for the re-alignment and re-construction of the 1,999 -foot Tippecanoe Street.

Existing Conditions:

Tippecanoe Street is presently 2,588 feet long, starting at Constance Boulevard and ending at the present cul-de-sac. The street is rural with ditches and gravel surface. The graded top surface width is approximately 26 feet, constructed for a future 26-foot-wide bituminous surface with curb and gutter.

Tippecanoe Street makes a sharp turn to the west just south of Constance Boulevard and follows Anoka County Ditch #11. The approximate first 500 feet is shown over a Rifle Peat area per the Anoka County Soils map. No soil borings have been taken to confirm the existence of peat under the present street. Borings should be taken before final preparation of plans.

A City owned parcel I.D. 14-32-23-31-0012 exists between 15990 and 15926 Tippecanoe Street which is 66-feet in width.

Soils:

Soils were evaluated using the Anoka County Soils Map. The soils in the area consist of Zimmerman Fine Sand, Lino Loamy Fine Sand, Isanti Fine Sandy Loam and Rifle Mucky Peat (Figure 2). Zimmerman Fine Sand is suitable for road subbase and is generally well drained. The suitable cut material will be used for fill. This soil generally covers the higher ground. Lino Loamy Fine Sand is a poorly drained soil with a relatively high-water table and will require placement of suitable fill from site excavation or imported soils for roadway construction. Isanti Fine Sandy Loam is in narrow low-lying areas near organic soils. It has high water tables and is poorly drained, usually requiring proper drainage and/or placement of suitable fill for roadway construction. Due to the high-water tables, the Isanti Fine Sandy Loam is not suitable for stormwater infiltration. A low area exists approximately 1,200 feet south of Constance Boulevard extending for approximately 150 feet. This is an area of Rifle Peat. The estimated excavation and granular borrow quantities are included in the estimated project cost.

Wetlands and Flood Zone:

Wetlands most likely exist in the ditches of the existing roadway but most likely do not exist elsewhere on the proposed improvements. Figure 4 illustrates the approximate wetland locations based on the National Wetland Inventory. Wetlands affected by the proposed improvements would be delineated prior to beginning preparation of plans. The Flood Zone Map, Figure 5, indicates there are no flood zones within the project limits.

Right-of-Way and Easements:

It is anticipated that approximately 16,719 square feet of easement will be required for the roadway and stormwater treatment. The City Attorney on the July 15, 2020 Council began negotiations to acquire this land shown on Figure 13. There is a 50-foot wide prescriptive easement on each side of the County Ditch 11 centerline.

Proposed Improvements:

The proposed improvement will prepare the existing surface for a 9-ton 26-foot wide with curb and gutter, and 6 1/2 inches of class 5 per City Standards. Tippecanoe Street from Constance Boulevard to 162nd Lane and 162nd Lane from Tippecanoe Street to the west plat border are being constructed to a 9-ton street section due to the Bug Company at 15941 Tippecanoe Street.

The improvement would include storm sewer, an infiltration basin and a pond. Note the typical street section on Exhibit 7.

A City owned parcel exists between 15990 and 15926 Tippecanoe Street which is 66-feet in width that can potentially be the 160th Avenue right-of-way. Figure 11 shows the potential thoroughfare from Tippecanoe Street westerly. The existing cul-de-sac exceeds the City's requirement for length.

Cost Estimate:

The project cost estimates are based on anticipated 2022 construction prices plus a 17% project development cost, an 8% engineering and inspection cost, and a 5% contingency cost (Figure 3). The final design has not been completed and therefore unknown work is not included in the estimate. Where additional costs may arise are additional subgrade correction and storm water treatment.

The final design has not been completed, and therefore unknown work is not included in the estimate. The estimated project cost is \$ 1,051,950.02.

Anticipated Revenues:

City policy is to assess benefited parcels for the improvement. The total number of assessments is 8 active assessments and 4 deferred assessments. The seven properties on the west side of Tippecanoe Street will be actively assessed. The property on the east side of Tippecanoe has potential to be split into four parcels for deferred assessments and one active assessment.


Estimated Construction Cost	\$ 1	,051,950.02	
8 Active Assessments (\$20,000/Each)	\$	160,000.00	(15.2%)
4 Deferred Assessments (\$20,000/Each)	\$	80,000.00	(7.6%)
City Contribution	\$	811,950.02	(77.2%)

Sincerely,

RFC Engineering, Inc.

Tom Collins, P.E.

Ham Lake City Engineer



200

Description

LOCATION MAP

Project

TIPPECANOE STREET FEASIBILITY STUDY

Drawn

EMP


Date 6/17/21 Project No. 2102.053

Figure No.

13635 Johnson Street Ham Lake, MN 55304

Voice: 763.862.8000 Fax: 763.862.8042





Sheet Title: SOILS MAP

Project:

FEASIBILITY STUDY TIPPECANOE STREET

Drawn: EMP Date: 6/17/2021

Project No. 2102.053

Figure No.


13635 Johnson Street Ham Lake, MN 55304 Telephone (763) 862-8000 Fax (763) 862-8042




CONSTRUCTION COST ESTIMATE TIPPECANOE STREET SOUTH OF CONSTANCE BOULEVARD

6/17/2021

ITEM			EST	UNIT	
NUMBER	ITEM DESCRIPTION	UNIT		PRICE	TOTAL
2021.501	MOBILIZATION	LUMP SUM	1	\$59,000.00	\$59,000.00
2101.505	CLEARING	ACRE	1	\$9,313.17	\$9,313.17
2101.505	GRUBBING	ACRE	1	\$4,496.03	\$4,496.03
2104.502	SALVAGE MAIL BOX SUPPORT	EACH	11	\$1.82	\$20.02
2104.503	SAWING CONCRETE PAVEMENT (FULL DEPTH)	LIN FT	32	\$5.35	\$171.20
2104.503	SAWING BITUMINOUS PAVEMENT (FULL DEPTH)	LIN FT	26	\$4.17	\$108.42
2104.503	REMOVE GUARDRAIL	LIN FT	116	\$5.35	\$620.60
2104.504	REMOVE CONCRETE DRIVEWAY PAVEMENT	SQ YD	67	\$13.16	\$881.72
2105.501	COMMON EXCAVATION	CU YD	1,915	\$20.87	\$39,966.05
2105.504	GEOTEXTILE FABRIC TYPE 1	SQ YD	400	\$4.07	\$1,628.00
2105.507	MUCK EXCAVATION (LV)	CU YD	1,522	\$19.15	\$29,146.30
2105.521	GRANULAR BORROW (CV)	CU YD	2,821	\$27.50	\$77,577.50
2105.607	CHANNEL AND POND EXCAVATION	CU YD	680	\$56.71	\$38,562.80
2211.501	AGGREGATE BASE, CLASS 5 OR 7	TON	2,692	\$23.75	\$63,935.00
2211.507	AGGREGATE BASE CLASS 5 - DRIVEWAY	CU YD	38	\$63.99	\$2,431.62
2360.504	TYPE SP 9.5 WEARING COURSE MIXTURE (2C) COMM. DRIVEWAY 1.0" THICK	SQ YD	2	\$16.48	\$32.96
	TYPE SP 12.5 WEARING COURSE MIXTURE (2;B) DRIVEWAY 2.0" THICK	SQ YD	14	\$11.88	\$166.32
2360.509	TYPE SP 9.5 WEARING COURSE MIXTURE (2,B OR C)	TON	738.0	\$97.16	\$71,704.08
2360.509	TYPE SP 12.5 WEARING COURSE MIXTURE (2;C)	TON	738	\$85.60	\$63,172.80
2501.502	24" CS PIPE APRON	EACH	5	\$824.97	\$4,124.85
2501.602	TRASH GUARD FOR 24" PIPE APRON	EACH	5	\$1,188.77	\$5,943.85
2503.503	24" CP PIPE SEWER	LIN FT	162.0	\$74.04	\$11,994.48
2503.511	15" RC PIPE SEWER CLASS IV	LIN FT	874.0	\$72.97	\$63,775.78
2503.511	18" RC PIPE SEWER CLASS IV	LIN FT	915	\$84.53	\$77,344.95
2506.502	CONSTRUCT DRAINAGE STRUCTURE DESIGN SPECIAL 1	EACH	6	\$2,518.78	\$15,112.68
2506.602	CATCH BASIN	EACH	6	\$3,323.42	\$19,940.52
2511.501	RANDOM RIPRAP CLASS III	CU YD	40	\$19.26	\$770.40
2531.501	CONCRETE CURB & GUTTER DESIGN D312 (MODIFIED)	LIN FT	4,062	\$15.62	\$63,448.44
2531.504	6" CONCRETE DRIVEWAY PAVEMENT	SQ YD	66.8	\$81.96	\$5,474.93
2540.602	INSTALL MAIL BOX SUPPORT-SWING TYPE	EACH	11	\$159.43	\$1,753.73
2563.601	TRAFFIC CONTROL	LUMP SUM	1	\$10,453.90	\$10,453.90
2564.531	SIGN PANELS TYPE C	SQ FT	59	\$59.81	\$3,528.79
2573.501	STABILIZED CONSTRUCTION EXIT	LUMP SUM	1	\$4,711.85	\$4,711.85
2573.502	SILT FENCE, TYPE HEAVY DUTY	LIN FT	2,000	\$3.00	\$6,000.00
2573.502	STORM DRAIN INLET PROTECTION	EACH	14	\$179.23	\$2,509.22
2573.560	CULVERT END CONTROLS	EACH	6	\$285.48	\$1,712.88
2574.507	COMMON TOPSOIL BORROW	CU YD	482	\$33.49	\$16,142.18
2575.605	TURF ESTABLISHMENT	ACRE	2.0	\$6,741.00	\$13,482.00
			•	•	
	TOTAL ESTIMATED CONSTRUCTION COST				\$791,160.02
	PROJECT DEVELOPMENT COSTS (17%)				\$134,497.20
	CONSTRUCTION ENGINEERING & INSPECTION COSTS (8%)				\$63,292.80
	LAND ACQUISITION				\$63,000.00
	TOTAL PROJECT COST				\$1,051,950.02
	8 Active Assessments (\$20,000/Each)				\$160,000.00
ĺ	4 Deferred Assessments (\$20,000/Each)				\$80,000.00
	City Cost				\$811,950.02








FEASIBILITY STUDY TIPPECANOE STREET

Ham Lake, MN 55304 Telephone (763) 862-8000 Fax (763) 862-8042









TYPICAL STREET SECTION COMMERCIAL 9-TON RFC-366B12

NOT TO SCALE

Sheet Title
PROPOSED TYPICAL SECTION

Drawn CSA Date 6/17/21

Project No. 2102.053


Figure No.

Project

TIPPECANOE STREET FEASIBILITY STUDY

13635 Johnson Street Ham Lake, MN 55304 Telephone (763) 862-8000 Fax (763) 862-8042





Description

PROPOSED IMPROVEMENTS

Drawn CSA Date 6/17/21

Project No. 2102.053


Sheet No.


Project


TIPPECANOE STREET FEASIBILITY STUDY


13635 Johnson Street Ham Lake, MN 55304

Voice: 763.862.8000 Fax: 763.862.8042 Engineering, Inc.









SKETCH AND DESCRIPTION ANOKA COUNTY HIGHWAY RIGHT OF WAY PLAT NO. 21 ~for~ RFC ENGINEERING (COUNTY ROAD NO. 60) CONSTANCE BOULEVARD That part of the east 94.00 feet of the west 500.00 feet of the Southeast Quarter of the Northwest Quarter of Section 14, Township 32, Range 23, Anoka County, Minnesota, lying southerly of the southerly right-of-way line of Tippecanoe Street N.E. as described in Document Number 598435 and northerly of the following described CENTERLINE OF NO. 11 COUNTY DITCH NO. 11 Commencing at the southeast corner of said west 500 feet of the Southeast Quarter of the Northwest Quarter of Section 14; thence on an assumed bearing of North 0 degrees 29 minutes 51 seconds East along the east line of said west 500.00 feet of the Southeast Quarter of the Northwest Quarter of Section 14 a distance of 878.06 feet to the point of beginning of the line to be described; thence North 89 degrees 30 minutes 09 seconds West a distance of 2.00 feet; thence 144.51 feet TIPPECANOE STREE southwesterly along a tangential curve, concave to the southeast, said curve having a radius of 92.00 feet and a central angle of 90 degrees 00 minutes 00 seconds to the west line of the east 94.00 feet of said west 500.00 feet of the Southeast Quarter of the Northwest Quarter of Section 14 and said line there terminating. AS DESCRIBED IN My DOC. NO. 598435 PROPOSED RIGHT-OF-WAY 16,719 SQ. FT. 🚫 **NORTH** PROPOSED 99 N89°30'09"W 162ND LANE NE **2.00**, P.30° 00'00" STREE1 94.00 TIPPECANOE 127.00 500.00 33 33 WEST LINE OF THE SE 1/4 OF THE NW 1/4 OF SEC. 14 N0°29'51"E 878.06 TIPPECANOE S0°29'51"W 787.77 IE OF THE EAST 94.00 FEET WEST 500 FEET OF THE SE OF THE NW 1/4 OF SEC. 14 EAST LINE OF THE WEST 500 FEET OF THE SE 1/4 OF THE NW 1/4 OF SEC. 14 94.00 -N89°27'25"E 94.03 SE CORNER OF THE SOUTH LINE OF THE WEST 500 FEET OF SE 1/4 OF THE NW THE SE 1/4 OF THE 1/4 OF SEC. 14 NW 1/4 OF SEC. 14 (EAST-WEST QUARTER LINE) Figure 13 DATUM: Assumed JOB NO. 201003ED I hereby certify that this plan, survey or report was prepared by E.G. RUD & SONS, INC. me or under my direct supervision and that I am a duly Licensed SCALE: 1'' = 60**REVISIONS** Land Surveyor under the laws of the State of Minnesota. **Professional Land Surveyors** DATE: 9/4/2020 6776 Lake Drive NE, Suite 110 DRAWN BY: BPN Lino Lakes, MN 55014 Minnesota License No. 41578 Tel. (651) 361-8200 Fax (651) 361-8701 www.egrud.com 3 September 2020. Dated <u>8th</u> day of CREW: NO. DATE DESCRIPTION