

PLAN SYMBOLS

EXISTING

PROPOSED

CENTERLINE

EXISTING

PROPOSED

RIGHT-OF-WAY LINE

CONSTRUCTION

PERMANENT

EASEMENT LINE

LOT

SECTION

PROPERTY LINE

CONSTRUCTION LIMITS

CLEAR ZONE

CONSTRUCTION LIMITS  
CLEAR ZONE

901

900

INTERMEDIATE

INDEX

901.25

901

GRADE BREAK

INTERMEDIATE

900

901.25

INTERMEDIATE

GRADE BREAK

EXISTING

PROPOSED

EXISTING CONTOURS

901

900

INTERMEDIATE

INDEX

901.25

901

GRADE BREAK

INTERMEDIATE

EXISTING

PROPOSED

PROPOSED CONTOURS

EXISTING

PROPOSED

DITCH LINE

EXISTING COUNTY

EXISTING COUNTY

X

X

X

FENCE LINE -- ANY TYPE

O

O

O

O

SILT FENCE

W

W

W

WETLAND BOUNDARY

TREE LINE

TREE SYMBOLS

EXISTING TREES (TO REMAIN)

X BM

O

BENCH MARK / IRON MONUMENT

Light Pole

Bollard

LIGHT POLE / BOLLARD

O

SOIL BORING

Building

BUILDING

Riprap

RIPRAP

Mailbox

MAILBOX

EXISTING

PROPOSED

SIGN

UTILITY SYMBOLS

GAS

GAS

GAS LINE

PETRO

PETRO

PETROLEUM LINE

OHE

OHE

OVERHEAD

UNDERGROUND

ELECTRIC

UGE

UGE

UNDERGROUND TELEPHONE LINE

T

T

T

UNDERGROUND CABLE TV LINE

CATV

CATV

UNDERGROUND FIBER OPTIC LINE

FO

FO

PRIVATE

MnDOT

TELEPHONE STRUCTURES

MANHOLE

JUNC. BOX

ELECTRIC JUNC. BOX

TV

CABLE TV JUNC. BOX

F

F

FIBER OPTIC STRUCTURES

EXISTING

PROPOSED

POWER POLE AND GUY WIRE

EXISTING

PROPOSED

STORM DRAIN LINE

EXISTING

PROPOSED

FLARED END SECTION

EXISTING

PROPOSED

CATCH BASIN

EXISTING

PROPOSED

MANHOLE

W

WELL

HATCH LEGEND

ROCK

HYDROMULCH

EROSION CONTROL

TREES

BITUMINOUS

REMOVAL

PLOT DATE: 5/29/2025 16:46



# MINNESOTA DEPARTMENT OF TRANSPORTATION

City of Ham Lake, Minnesota

## CONSTRUCTION PLANS FOR GRADING, AGGREGATE BASE, PLANT MIXED BITUMINOUS SURFACING, STORM DRAINS, STORM POND CONSTRUCTION, AND CONCRETE CURB AND GUTTER

CHISHOLM STREET FROM 334 FEET SOUTH OF CROSSTOWN BOULEVARD (CSAH 18) TO 173RD LANE, 173RD LANE FROM CHISHOLM STREET TO BALTIMORE STREET, BALTIMORE STREET FROM 173RD LANE TO 64 FEET SOUTH OF 171ST AVENUE.

HAM LAKE PROJECT NO. 2111  
STATE PROJECT NO. 0208-170  
STATE AID PROJECT NO. 197-119-003



SAP 197-119-003	
GROSS LENGTH	2,473 FEET
GROSS LENGTH	0.468 MILES
BRIDGE LENGTH	FEET
EXCEPTIONS LENGTH	FEET
NET LENGTH	2,473 FEET
NET LENGTH	0.468 MILES
FROM REF. POINT 334' SOUTH OF CROSSTOWN BLVD	

TO REF. POINT 64. FT. SOUTH OF 171ST AVE

SP 0208-170	
GROSS LENGTH	2,473 FEET
GROSS LENGTH	0.468 MILES
BRIDGE LENGTH	FEET
EXCEPTIONS LENGTH	FEET
NET LENGTH	2,473 FEET
NET LENGTH	0.468 MILES
FROM REF. POINT 021+00.205	

TO REF. POINT 021+00.707

BALTIMORE STREET  
STATE PROJECT NO. 197-119-003

ADT (2023)	300	ADT (2043)	450
Design Speed	30 MPH		
NO. OF TRAFFIC LANES	2	NO. OF PARKING LANES	0
FUNCTIONAL CLASSIFICATION	COLLECTOR, LOW DENSITY		
SOIL FACTOR	50%	HCA DT	<150
TON DESIGN	9 TON		
STOPPING SIGHT DISTANCE BASED ON:			
HEIGHT OF EYE 3.5'			
HEIGHT OF OBJECT 2.0'			
Design Speed not achieved at:			
STA. N/A	TO STA. N/A		
TOWNSHIP 32, RANGE 23, SECTION 5 & 8			

AGREEMENT NO. 1053661  
CITY OF HAM LAKE  
SP 0208-170 (TH65=005)  
STATE FUNDS  
METRO DISTRICT

THE SUBSURFACE UTILITY INFORMATION IN THIS PLAN IS UTILITY QUALITY LEVEL D. THIS UTILITY QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE 38-22, ENTITLED "STANDARD GUIDELINES FOR THE INVESTIGATING AND DOCUMENTING EXISTING UTILITIES."

THE UTILITIES SHOWN ARE BASED UPON THE BEST INFORMATION AVAILABLE AND MAY NOT REFLECT THE ACTUAL EFFECTS ON THE UTILITIES BY CONSTRUCTION. ACTUAL DETERMINATIONS WILL BE MADE IN THE FIELD DURING CONSTRUCTION.

PLAN REVISIONS		
DATE	SHEET NO.	APPROVED BY

STATE PROJ. NO.	CHARGE	IDENTIFIER
0208-170		
197-119-003		

### STATE FUNDS

#### GOVERNING SPECIFICATIONS

THE 2020 EDITION OF THE MINNESOTA DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION" SHALL GOVERN.

ALL TRAFFIC CONTROL DEVICES AND SIGNING SHALL CONFORM TO THE 2024 MnMUTCD, INCLUDING FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL ZONE LAYOUTS.

#### INDEX

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	STATEMENT OF ESTIMATED QUANTITIES AND STANDARD PLATES
3-4	EATHWORK SUMMARY AND TABULATIONS
5	UTILITY TABULATIONS
6	TYPICAL SECTION AND DETAILS
7-8	DETAILS
9-16	MNDOT STANDARD PLANS
17	RETAINING WALL DETAIL
18	INTERSECTION DETAILS
19-20	TREE REMOVAL PLAN
21-22	REMOVAL PLAN
23-24	PLAN AND PROFILE
25-26	GRADING AND DRAINAGE PLAN
27-30	STORM DETAILS
31-33	STORMWATER POLLUTION PREVENTION PLAN
34-35	SIGNING AND STRIPING PLAN
36-42	CROSS SECTIONS
43	CROSS SECTION FOR MUCK ESTIMATION ONLY

THIS PLAN CONTAINS 43 SHEETS

ALL APPLICABLE FEDERAL, STATE AND LOCAL LAWS AND ORDINANCES WILL BE COMPLIED WITH IN THE CONSTRUCTION OF THIS PROJECT.

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

SIGNED: David A. Krugler

DATE: 5/29/25 REG. NO. 48768

APPROVED: Khani Sahebjam CITY ENGINEER - HAM LAKE

APPROVED: Khani Sahebjam METRO DISTRICT ENGINEER

DISTRICT STATE AID ENGINEER: REVIEWED FOR COMPLIANCE WITH STATE AID RULES/POLICY

FOR Dan Erickson APPROVED FOR STATE AID FUNDING: STATE AID ENGINEER

STATE AID PROJECT NO. 197-119-003  
STATE PROJECT NO. 0208-170 (TH65=005)

RFC ENGINEERING, INC.  
Consulting Engineers

13635 Johnson Street NE Telephone 763-862-8000  
Ham Lake, MN 55304 Fax 763-862-8042

JOB NO. 2111 SHEET NO. 1 OF 43 SHEETS  
FILE: 33-2-101

STATEMENT OF ESTIMATED QUANTITIES									
TAB	SHEET	NOTES	ITEM NO.	ITEM	UNIT	ENTIRE PROJECT	S.A.P. 197-119-003 & S.P. 0208-170		NON-PARTICIPATING
						ESTIMATED QUANTITIES	ROADWAY	STORM SEWER	ROADWAY
							ESTIMATED QUANTITIES	ESTIMATED QUANTITIES	
			2021.501	MOBILIZATION	LUMP SUM	1	1		
AD	3		2101.502	CLEARING	EACH	19	19		
AD	3		2101.502	GRUBBING	EACH	19	19		
AD	3		2101.505	CLEARING (P)	ACRE	4.51	4.51		
AD	3		2101.505	GRUBBING (P)	ACRE	4.51	4.51		
AA	3	6	2104.502	REMOVE SIGN	EACH	6	2		4
AJ	3		2104.502	SALVAGE CASTING	EACH	2	2		
AC	3		2104.502	SALVAGE LIGHT POLE	EACH	4			4
AB	3	6	2104.502	SALVAGE SIGN	EACH	6	1		4
		10	2104.502	SALVAGE MAIL BOX SUPPORT AND MAILBOX	EACH	1	1		
	3		2104.502	ABANDON AND SEAL WELL SHAFT	EACH	1	1		
AG	3		2104.503	SAWING CONCRETE PAVEMENT (FULL DEPTH)	LIN FT	8	8		
AF	3		2104.503	SAWING BITUMINOUS PAVEMENT (FULL DEPTH)	LIN FT	691	654		37
AM	3		2104.503	REMOVE CONCRETE CULVERT	LIN FT	4	4		
AM	3		2104.503	REMOVE METAL CULVERT	LIN FT	29			29
AH	3		2104.503	REMOVE CURB AND GUTTER	LIN FT	142	142		
AL	3		2104.504	REMOVE BITUMINOUS DRIVEWAY PAVEMENT	SQ YD	1 036	975		61
AK	3		2104.504	REMOVE BITUMINOUS PAVEMENT	SQ YD	1 000	1 000		
AM	3	4	2106.507	EXCAVATION - COMMON (P)	CU YD	4 787	4 065		294
AM	3,4,3	4, 11	2106.507	EXCAVATION - MUCK (P)	CU YD	2 111	2 111		428
AM	3	4	2106.507	EXCAVATION - CHANNEL AND POND (P)	CU YD	17 843	17 843		
AM	3	4	2106.507	COMMON EMBANKMENT - STOCKPILE (CV) (P)	CU YD	5 460			5 460
AM	3	4	2106.507	COMMON EMBANKMENT (CV) (P)	CU YD	12 982	12 982		
		11	2108.504	GEOTEXTILE FABRIC TYPE 5	SQ YD	2 040	2 040		
BA	4		2211.509	AGGREGATE BASE CLASS 5	TON	3 302	3 302		
BJ	4	8	2211.604	AGGREGATE BASE (CV) CLASS 5 6.0" THICK-DRIVEWAY	SQ YD	245	245		
BF	4	8	2360.504	TYPE SP 9.5 WEARING COURSE MIXTURE (3,C) 1.0" THICK-DRIVEWAY	SQ YD	154	154		
BK	4	8	2360.504	TYPE SP 12.5 WEARING COURSE MIXTURE (3,C) 2.0" THICK-DRIVEWAY	SQ YD	154	154		
BB	4	9	2360.509	TYPE SP 9.5 WEARING COURSE MIXTURE (3,C)	TON	985	985		
BC	4	9	2360.509	TYPE SP 12.5 WEARING COURSE MIXTURE (3,C)	TON	985	985		
BM	4,13-17		2411.604	MODULAR BLOCK RETAINING WALL	SQ YD	80	80		
	27-30	1, 5	2501.502	15" GS PIPE APRON	EACH	1		1	
	27-30	1, 5	2501.502	18" GS PIPE APRON	EACH	2		2	
	27-30	1, 5	2501.502	24" GS PIPE APRON	EACH	3		3	
	27-30	1, 5	2501.502	30" GS PIPE APRON	EACH	2		2	
	27-30	1, 5	2501.502	36" GS PIPE APRON	EACH	1		1	
	27-30	1, 5	2501.502	18" RC PIPE APRON	EACH	8		8	
	8		2501.602	POND OUTLET BAFFLE	EACH	5		5	
	27-30	1, 5	2501.602	TRASH GUARD FOR 15" PIPE APRON	EACH	1		1	
	27-30	1, 5	2501.602	TRASH GUARD FOR 18" PIPE APRON	EACH	10		10	
	27-30	1, 5	2501.602	TRASH GUARD FOR 24" PIPE APRON	EACH	3		3	
	27-30	1, 5	2501.602	TRASH GUARD FOR 30" PIPE APRON	EACH	2		2	
	27-30	1, 5	2501.602	TRASH GUARD FOR 36" PIPE APRON	EACH	1		1	
	27-30	1, 5	2503.503	15" CP PIPE SEWER (SMOOTH)	LIN FT	16		16	
	27-30	1, 5	2503.503	18" CP PIPE SEWER (SMOOTH)	LIN FT	51		51	
	27-30	1, 5	2503.503	24" CP PIPE SEWER (SMOOTH)	LIN FT	117		117	
	27-30	1, 5	2503.503	30" CP PIPE SEWER (SMOOTH)	LIN FT	38		38	
	27-30	1, 5	2503.503	36" CP PIPE SEWER (SMOOTH)	LIN FT	36		36	
	27-30	1, 5	2503.503	12" RC PIPE SEWER DESIGN 3006 CLASS IV	LIN FT	126		126	
	27-30	1, 5	2503.503	15" RC PIPE SEWER DESIGN 3006 CLASS IV	LIN FT	497		497	
	27-30	1, 5	2503.503	18" RC PIPE SEWER DESIGN 3006 CLASS IV	LIN FT	613		613	
	27-30	1, 5	2503.503	24" RC PIPE SEWER DESIGN 3006 CLASS IV	LIN FT	567		567	
	27-30	1, 5	2503.503	36" RC PIPE SEWER DESIGN 3006 CLASS IV	LIN FT	209		209	
	27	1, 5	2503.602	CONNECT TO EXISTING STORM SEWER	EACH	1		1	
	27-30		2503.602	18" PIPE PLUG	EACH	4		4	
	23		2504.602	DEVELOP WELL	EACH	1			1
	27-30	2, 5	2506.502	CONSTRUCT DRAINAGE STRUCTURE DESIGN SPECIAL-2X3	EACH	5		5	
	27-30	2, 5	2506.502	CONSTRUCT DRAINAGE STRUCTURE DESIGN SPECIAL 1-48"	EACH	6		6	
	27-30	2, 5	2506.502	CONSTRUCT DRAINAGE STRUCTURE DESIGN SPECIAL 2-60"	EACH	1		1	
	27-30	2, 5	2506.502	CONSTRUCT DRAINAGE STRUCTURE DESIGN SPECIAL 3-84"	EACH	1		1	
	27-30	2, 5	2506.502	CONSTRUCT DRAINAGE STRUCTURE DESIGN SPECIAL 4-60" SUMP	EACH	3		3	
	27-30	2, 5	2506.502	CONSTRUCT DRAINAGE STRUCTURE DESIGN SPECIAL 5-72" SUMP	EACH	1		1	
	27-30	2, 5	2506.502	CONSTRUCT DRAINAGE STRUCTURE DESIGN SPECIAL 6-96" SUMP	EACH	2		2	
	27-30	2, 5	2506.502	CONSTRUCT DRAINAGE STRUCTURE DESIGN SPECIAL 7-48"	EACH	6		6	
BD	27	2, 5	2506.502	INSTALL SALVAGED CASTING	EACH	2		2	
BT	4	2	2511.504	GEOTEXTILE FILTER TYPE 4	SQ YD	315	315		
BH	4		2511.507	RANDOM RIPRAP CLASS III	CU YD	86	86		

STATEMENT OF ESTIMATED QUANTITIES									
TAB	SHEET	NOTES	ITEM NO.	ITEM	UNIT	ENTIRE PROJECT	S.A.P. 197-119-003 & S.P. 0208-170		NON-PARTICIPATING
						ESTIMATED QUANTITIES	ROADWAY	STORM SEWER	ROADWAY
							ESTIMATED QUANTITIES	ESTIMATED QUANTITIES	
BL	4		2531.503	CONCRETE CURB AND GUTTER DESIGN B612	LIN FT	187	187		
BO	4		2531.503	CONCRETE CURB AND GUTTER DESIGN B618	LIN FT	4 900	4 900		
BP	4	8	2531.504	6" CONCRETE DRIVEWAY PAVEMENT	SQ YD	72	72		
BG	4,30		2531.603	CONCRETE GUTTER DESIGN - TRENCH DRAIN	LIN FT	440	440		
		10	2540.602	INSTALL MAIL BOX SUPPORT WITH MAILBOX	EACH	1	1		
			2563.601	TRAFFIC CONTROL	LUMP SUM	1	1		
			2564.502	RIGHT OF WAY MARKER	EACH	1	1		
BN	4	6	2564.518	SIGN PANELS TYPE C	SQ FT	69	69		
BV	4	6	2564.602	INSTALL SALVAGED SIGNS	EACH	2	1		1
	31-33	7	2573.501	STABILIZED CONSTRUCTION EXIT	LUMP SUM	1	1		
BR	4,31-33	7	2573.502	STORM DRAIN INLET PROTECTION	EACH	25	25		
BS	4,31-33	7	2573.502	CULVERT END CONTROLS	EACH	20	20		
BQ	4,31-33	7	2573.503	SILT FENCE, TYPE MS	LIN FT	6 621	6 174		447
	31-33	3	2575.605	TURF ESTABLISHMENT (25-131 SEEDING MIX)	ACRE	5.16	4.39		0.77
	31-33	3	2575.605	TURF ESTABLISHMENT (33-261 SEEDING MIX)	ACRE	2.86	2.86		
BU	4,34-35		2582.503	4" WHITE SOLID LINE EPOXY PAINT	LIN FT	89	89		
BE	4,34-35		2582.503	4" DOUBLE YELLOW SOLID LINE PAINT	LIN FT	2 400	2 400		

NOTES:

1. SELECT GRANULAR BORROW, STRUCTURAL EXCAVATION, AND GRANULAR BACKFILL FOR STORM PIPES ARE INCIDENTAL.
2. FILTER FABRIC AND FABRIC WRAP FOR CATCH BASINS AND MANHOLES ARE INCIDENTAL.
3. ALL DISTURBED AREAS DETERMINED NOT TO BE PAVED, AGGREGATE SURFACE, CONCRETE SURFACE OR RIPRAPPED SHALL HAVE 4 INCHES OF TOPSOIL. FERTILIZER TYPE 2, MULCH MATERIAL, AND SEED MIXTURE NO. 33-261, MULCH TYPE 3 (WEED FREE MULCH) WITH NO FERTILIZER AND SEED MIXTURE. NO. 25-131 PER MNDOT STANDARD SPECIFICATION 3876, APPLY TYPE 1 HYDROMULCH AT THE RATE OF 2 (TWO) TONS PER ACRE OR A HYDRAULIC SOIL STABILIZER OR BONDED FIBER MATRIX (TO ACHIEVE A 90% UNIFORM GROUND COVERAGE). SEED MIXTURE, WATER, TYPE 2 FERTILIZER, AND MULCH ARE INCIDENTAL. SOIL TESTING TO DETERMINE FERTILIZER MIXTURE RATIO AND RATE OF APPLICATION IS INCIDENTAL.
4. MATERIAL FOUND IN THE SUBCUTS THAT IS UNSUITABLE FOR FILL IN THE ROADBED SHALL BE REMOVED OFF-SITE.
5. THE CONTRACTOR SHALL NOT DISTURB AREAS OUTSIDE THE CONSTRUCTION LIMITS.
6. SIGNS INCLUDE POSTS.
7. INSTALLATION AND MAINTENANCE ARE INCIDENTAL.
8. QUANTITY SHOWN USED FOR DRIVEWAY CONSTRUCTION. SEE DETAIL RFC-370A1.
9. BITUMINOUS MATERIAL FOR TACK COAT SHALL BE INCIDENTAL.
10. REMOVE SUPPORTS AND SALVAGE MAIL BOXES. SALVAGE MAIL BOXES ARE INCIDENTAL.
11. NO MUCK IS ANTICIPATED. STA 24+00 TO 26+00 MAY ENCOUNTER MUCK. STA 24+00 TO 26+00 USED FOR QUANTITY ESTIMATION. **ADDED FOR BUDGETING PURPOSE ONLY.** IF MUCK IS ENCOUNTERED, ALL MUCK SHALL BE DELIVERED TO THE HAM LAKE PUBLIC WORKS SHOP.

SEED MIX 25-131: COMMERCIAL TURF  
MULCH TYPE 1  
PLANT APRIL 1ST - JUNE 1ST FOR SPRING PLANTING OR  
JULY 20TH - SEPTEMBER 20TH FOR FALL PLANTING

SEED MIX 33-261: PONDS & WET AREAS IN CENTRAL, SOUTHERN AND WESTERN MN  
MULCH TYPE 3  
PLANT APRIL 15TH - JULY 20TH FOR SPRING PLANTING OR  
SEPTEMBER 20TH - OCTOBER 20TH FOR FALL PLANTING


BASIS FOR ESTIMATED QUANTITIES

AGGREGATE BASE 105 LBS/S.Y./INCH  
BITUMINOUS MIXTURE 110 LBS/S.Y./INCH  
TACK COAT 0.05 GAL./S.Y.  
TYPE I MULCH 2 TONS/ACRE

PLATE NO.	STANDARD PLATES - RFC ENGINEERING (IN THE PLANS)
RFC-356A2	TRANSITION CURB: D312M TO B618
RFC-356A4	TRANSITION CURB: D412M TO B612
RFC-356A10	TRANSITION CURB: D412M TO B618
RFC-356B	TRANSITION CURB: B612 TO B618
RFC-365A1	TYPICAL SUBGRADE EXCAVATION
RFC-365C4	TYPICAL FLOATING ROAD SECTION NEW ROAD CONSTRUCTION
RFC-366B1	TYPICAL STREET SECTION
RFC-370A1	COMMERCIAL DRIVEWAY
RFC-380A	CURB END
RFC-459C	RECTANGULAR CATCH BASIN
RFC-463	FABRIC AROUND CATCH BASIN
RFC-465A1	RECTANGULAR INLET FOR ROUND MANHOLE
RFC-465A3	RECTANGULAR INLET FOR ROUND MANHOLE - VARIABLE SUMP
RFC-465C	ROUND MANHOLE
RFC-466B	RCP TRASH GUARD
RFC-466C	CPP TRASH GUARD
RFC-472B	TRENCH DRAIN DETAIL
RFC-654	STORM DRAIN BEDDING FOR RIGID AND FLEXIBLE PIPE *MNDOT DETAIL
RFC-850B2	POND OUTLET BAFFLE
RFC-852A1	EMERGENCY OVERFLOW WEIR
RFC-856A	FORESLOPE
RFC-856B	TYPICAL DITCH DETAIL
RFC-857	SILT FENCE AT FES
RFC-858A	TYPICAL DETENTION POND

THE FOLLOWING STANDARD PLATES, APPROVED BY THE FEDERAL HIGHWAY ADMINISTRATION, SHALL APPLY

PLATE NO.	MnDOT STANDARD PLATES
3000M	REINFORCED CONCRETE PIPE (6 SHEETS)
3006H	GASKET JOINT FOR R.C. PIPE (2 SHEETS)
3129A	METAL APRON FOR CORRUGATED POLYETHYLENE PIPE
3133D	RIPRAP AT RCP OUTLETS
3134D	RIPRAP AT CSP OUTLETS
3145C	CONCRETE PIPE OR PRECAST BOX CULVERT TIES
7100H	CONCRETE CURB & GUTTER
8000K	TEMPORARY CHANNELIZERS (3 SHEETS)
9350C	MAILBOX SUPPORT SWING-AWAY TYPE (3 SHEETS)



**800-252-1166 651-454-0002**  
PLOT DATE: 5/29/2025 16:46

UTILITIES: CENTURYLINK (763) 712-5017  
CENTERPOINT ENERGY (763) 323-2760  
COMCAST (952) 607-4078  
CONNEXUS ENERGY (763) 323-4268  
XCEL ENERGY (612) 526-4508

DATE	REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

*Dave Krueger*

DATE 05/29/25 REG. NO. 48768

**RFC ENGINEERING, INC.**  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
STATEMENT OF ESTIMATED QUANTITIES  
AND STANDARD PLATES

DWG: 2111 QTY 1  
DATE: 05/29/25  
JOB NUMBER: 2111  
SHEET: 2 OF 43  
FILE: 33-2-102

DESIGN BY: LDZ DRAWN BY: LDZ CHECKED BY: DAK

REMOVE SIGN					AA
STATION	LOCATION	SIGN NO.	POST	CODE NO.	PANEL LEGEND
9+68	BALTIMORE ST. – RT	C–21	SINGLE	R1–1	STOP
10+36	BALTIMORE ST. – LT	C–24	SINGLE		NOTICE
23+37	T.H. 65 – RT	C–26	SINGLE		DELINEATOR
23+83	T.H. 65 – RT	C–21	TRIPLE	R1–1	STOP
25+65	T.H. 65 – RT	C–20	SINGLE		CULVERT
25+79	T.H. 65 – RT	C–20	SINGLE		CULVERT
TOTAL			6		

SALVAGE SIGN					AB
STATION	LOCATION	SIGN NO.	POST	CODE NO.	PANEL LEGEND
10+03	BALTIMORE ST. – LT	C–22	SINGLE		NO TRESPASSING
10+19	BALTIMORE ST. – RT	C–23	SINGLE	R1–1	STOP & STREET
20+83	BALTIMORE ST. – LT	C–25	SINGLE		PRIVATE
22+82	BALTIMORE ST. – LT	C–25	DOUBLE		PRIVATE
23+77	BALTIMORE ST. – LT	C–27	SINGLE		RIGHT OF WAY
24+45	T.H. 65 – RT	C–28	TRIPLE	W3–3	SIGNAL AHEAD
TOTAL			6		

SALVAGE LIGHT POLES			AC
STATION	LOCATION	LIGHT POST NO.	TYPE
19+96	BALTIMORE ST. – RT	LP–20	SINGLE
20+57	BALTIMORE ST. – RT	LP–21	SINGLE
21+87	BALTIMORE ST. – RT	LP–22	SINGLE
22+87	BALTIMORE ST. – LT	LP–23	SINGLE
TOTAL			4

TREE REMOVAL					AD
STATION	LOCATION	CLEARING (ACRE)	GRUBBING (ACRE)	CLEARING (EACH)	GRUBBING (EACH)
10+18 TO 10+36	ROADWAY			7	7
16+80 TO 17+88	POND 1	0.45	0.45		
18+00	ROADWAY			4	4
24+26 TO 24+56	MNDOT DITCH			6	6
23+67 TO 32+19	ROADWAY	4.06	4.06		
32+34 TO 32+90	ROADWAY			2	2
TOTAL		4.51	4.51	19	19

PLANT SALVAGE (BY OTHERS)			AE
STATION	LOCATION	CATEGORY	TYPE
16+25	ROADWAY	WATCH LISTED	1
17+00	POND 1	WATCH LISTED	5
22+75	MNDOT DITCH	THREATENED	3
24+10 TO 26+00	ROADWAY	ENDANGERED	26
TOTAL WATCH LISTED			6
TOTAL THREATENED			3
TOTAL ENDANGERED			26
TOTAL PLANTS			35

SAWCUT BITUMINOUS PAVEMENT		AF
STATION	LOCATION	LIN FT
9+38	BALTIMORE ST. – ROADWAY	30
50+67	171ST AVE. – ROADWAY	30
19+97 TO 23+67	JAKE'S AUTO MALL – RT – PARKING LOT	368
23+34 TO 24+10	T.H. 65 – RT – DRIVEWAY	88
25+60 TO 25+76	T.H. 65 – RT – DRIVEWAY	37
34+11	CHISHOLM ST. – ROADWAY	29
34+11 TO 35+19	CHISHOLM ST. – RT – TEMP CDS	109
TOTAL		691

SAWCUT CONCRETE CURB		AG
STATION	LOCATION	LIN FT
9+38	BALTIMORE ST. – RT – ROADWAY	2
9+38	BALTIMORE ST. – LT – ROADWAY	2
34+11	CHISHOLM ST. – RT – ROADWAY	2
34+11	CHISHOLM ST. – LT – ROADWAY	2
TOTAL		8

REMOVE CONCRETE CURB AND GUTTER		AH
STATION	LOCATION	LENGTH (LIN FT)
9+38 TO 10+08	BALTIMORE ST. – RT	68
9+38 TO 9+86	BALTIMORE ST. – LT	70
34+09 TO 34+11	CHISHOLM ST. – RT	2
34+09 TO 34+11	CHISHOLM ST. – LT	2
TOTAL		142

REMOVE CULVERTS			AM
STATION	LOCATION	TYPE	LENGTH (LIN FT)
25+66 TO 25+79	T.H. 65 – RT	CMP	29
10+22 TO 10+26	BALTIMORE ST. – RT	RCP	4
TOTAL			33

SALVAGE CASTING		AJ
STATION	LOCATION	STRUCTURE NAME
9+73	BALTIMORE ST. – LT	EX CBMH 1
9+78	BALTIMORE ST. – RT	EX CBMH 2
TOTAL		2

REMOVE BITUMINOUS PAVEMENT		AK
STATION	LOCATION	SQ YD
9+38 TO 10+19	INTERSECTION OF BALTIMORE ST. & 171ST AVE.	455
34+11	CHISHOLM ST. – ROADWAY	7
34+11 TO 35+19	CHISHOLM ST. – RT – TEMP CDS	538
TOTAL		1,000

REMOVE BITUMINOUS DRIVEWAY		AL
STATION	LOCATION	SQ YD
10+03	DRIVEWAY – BALTIMORE ST. – LT	37
19+19 TO 23+67	JAKE'S AUTO MALL DRIVEWAY	938
25+60 TO 25+76	T.H. 65 – RT – DRIVEWAY	61
TOTAL		1036

EARTHWORK SUMMARY					AM
<div><div>EXCAVATION (CU YD)</div><div>TOPSOIL: COMMON 3,320 CU YD (EV) CHANNEL &amp; PONDS 2,636 CU YD (EV)  COMMON 1,467 CU YD (EV) CHANNEL &amp; PONDS 15,207 CU YD (EV)</div><div>22,630 CU YD (EV) ①</div><div>EXCAVATION (CU YD)</div><div>MUCK 2,111 CU YD (EV)</div></div>					<div><div>EMBANKMENT (CU YD)</div><div>TOPSOIL 5,368 CU YD (EV)/1.1 = 4,880 CU YD (CV) COMMON EX 8,691.8 CU YD (EV)/1.3 = 6,686 CU YD (CV) CHANNEL &amp; PONDS 2028.4 CU YD (EV)/1.1 = 1,844 CU YD (CV) ⑤ STOCKPILE 6,542 CU YD (EV)/1.3 = 5,032 CU YD (CV)</div><div>18,442 CU YD (CV) ②</div><div>EMBANKMENT (CU YD)</div><div>COMMON EX 2,111 CU YD (EV) = 2,111 CU YD (CV) ④ WASTE 2,111 CU YD (EV)</div></div>
<div>NOTES: ① TOTAL EXCAVATION (EV) REQUIRED FOR PROJECT. ② TOTAL EMBANKMENT (CV) REQUIRED FOR PROJECT. ③ USED FOR MUCK PRICING ESTIMATION ONLY. ④ TOPSOIL REQUIRED FOR SITE MY BE OBTAINED BY MIXING MUCK MATERIAL AND COMMON EX TO ACHIEVE 25% MAX ORGANIC. ⑤ STOCKPILE MATERIAL TO BE USED AS COMMON IF MUCK IS ENCOUNTERED.</div>					

- NOTES:
- TOP OF GRADING SUBGRADE IS DEFINED AS THE BOTTOM OF THE CLASS 5 AGGREGATE BASE.
  - BITUMINOUS AND CONCRETE DISTURBED BY CONSTRUCTION SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF OFFSITE IN ACCORDANCE WITH MnDOT SPEC. 2104.3C3.
  - COMPACTION OF ALL GRADING AND BASE ITEMS SHALL BE BY THE "QUALITY COMPACTION METHOD".
  - USE TACK COAT BETWEEN ALL BITUMINOUS LAYERS AND BETWEEN BITUMINOUS AND CONCRETE CURB AND GUTTER. TACK COAT IS INCIDENTAL.
  - STRIP ALL TOPSOIL AREAS TO BE DISTURBED BY CONSTRUCTION AND REUSE TOPSOIL OR USE AS FILL OUTSIDE OF ROAD CORE.
  - WHENEVER THE WORD "INCIDENTAL" IS USED IN THIS PLAN, IT SHALL MEAN THIS WORK SHALL BE INCIDENTAL FOR WHICH NO DIRECT COMPENSATION WILL BE MADE.
  - STATIONING FOR LOCATION OF EXISTING AND NEW SIGNS IS APPROXIMATE.
  - EXISTING BALTIMORE STREET IS APPROXIMATELY 3" TO 4" OF BITUMINOUS AND 6" OF CLASS 5.



UTILITIES: CENTURYLINK (763) 712–5017  
CENTERPOINT ENERGY (763) 323–2760  
COMCAST (952) 607–4078  
CONNEXUS ENERGY (763) 323–4268  
XCEL ENERGY (612) 526–4508

DATE	REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.  
*Dave Krueger*  
DATE 05/29/25 REG. NO. 48768

RFC ENGINEERING, INC.  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763–862–8000  
Fax 763–862–8042

DESIGN BY: LDZ DRAWN BY: LDZ CHECKED BY: DAK

S.A.P. 197–119–003 S.P. 0208–170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
EARTHWORK SUMMARY AND TABULATIONS

DWG:	2111 TAB 1
DATE:	05/29/25
JOB NUMBER:	2111
SHEET:	3 OF 43
FILE:	33–2–103

AGGREGATE BASE CLASS 5		BA
STATION TO STATION	LOCATION	TONS
9+38 TO 34+11	BALTIMORE ST. TO CHISHOLM ST.	3,232
50+15 TO 50+67	171ST AVE.	70
TOTAL		3,302

TYPE SP 9.5 BITUMINOUS WEARING COURSE MIXTURE (SPWEA340C)			BB
STATION TO STATION	LOCATION	SQ. YD. (2 IN)	TONS
9+38 TO 34+11	BALTIMORE ST. TO CHISHOLM ST.	7,968.9	964
50+15 TO 50+67	171ST AVE.	175.3	21
TOTAL			985

TYPE SP 12.5 BITUMINOUS WEARING COURSE MIXTURE (SPWEB340C)			BC
STATION TO STATION	LOCATION	SQ. YD. (2 IN)	TONS
9+38 TO 34+11	BALTIMORE ST. TO CHISHOLM ST.	7,968.9	964
50+15 TO 50+67	171ST AVE.	175.3	21
TOTAL			985

INSTALL SALVAGED CASTING		BD
STATION	LOCATION	STRUCTURE NAME
9+73	BALTIMORE ST. – LT	EX CBMH 1
9+78	BALTIMORE ST. – RT	EX CBMH 2
TOTAL		2

4” DOUBLE SOLID LINE YELLOW–PAINT		BE
STATION	LOCATION	LIN. FT.
9+38 TO 9+54	BALTIMORE STREET	16
50+48 TO 50+67	171ST AVENUE	19
10+46 TO 34+11	BALTIMORE ST. TO CHISHOLM ST. – CENTER	2,365
TOTAL		2,400

TYPE SP 9.5 BITUMINOUS WEARING COURSE MIXTURE (SPWEA340C) 1” – DRIVEWAY		BF
STATION TO STATION	LOCATION	SQ. YD.
9+83 TO 10+13	BALTIMORE ST. – LT NORTH CENTRAL MOTORS DRIVEWAY	26
20+24 TO 20+68	BALTIMORE ST. – RT JAKE’S AUTO MALL SOUTH DRIVEWAY	61
23+32 TO 23+72	BALTIMORE ST. – RT JAKE’S AUTO MALL NORTH DRIVEWAY	67
TOTAL		154

TRENCH DRAIN		BG
STATION	LOCATION	LIN FT
19+00 TO 20+14	BALTIMORE ST. – RT	114
19+97 TO 20+63	JAKE’S AUTO MALL DRIVEWAY – SOUTH	66
20+11	BALTIMORE ST. –RT	15
20+77 TO 23+22	BALTIMORE ST. –RT	245
TOTAL		440

6” CONCRETE PAVEMENT – DRIVEWAY		BP
STATION TO STATION	LOCATION	SQ. YD.
9+83 TO 10+13	BALTIMORE ST. – LT NORTH CENTRAL MOTORS DRIVEWAY	21
20+24 TO 20+68	BALTIMORE ST. – RT JAKE’S AUTO MALL SOUTH DRIVEWAY	26
23+32 TO 23+72	BALTIMORE ST. – RT JAKE’S AUTO MALL NORTH DRIVEWAY	25
TOTAL		72

4” SOLID SINGLE LINE WHITE–PAINT		BU
STATION	LOCATION	LIN. FT.
23+34 TO 24+10	T.H. 65 – RT	89
TOTAL		89

DRIVEWAY AGGREGATE BASE CLASS 5		BJ
STATION TO STATION	LOCATION	SQ. YD.
9+83 TO 10+13	BALTIMORE ST. – LT NORTH CENTRAL MOTORS DRIVEWAY	53
20+24 TO 20+68	BALTIMORE ST. – RT JAKE’S AUTO MALL SOUTH DRIVEWAY	94
23+32 TO 23+72	BALTIMORE ST. – RT JAKE’S AUTO MALL NORTH DRIVEWAY	98
TOTAL		245

TYPE SP 12.5 BITUMINOUS WEARING COURSE MIXTURE (SPWEB340C) 2” – DRIVEWAY		BK
STATION TO STATION	LOCATION	SQ. YD.
9+83 TO 10+13	BALTIMORE ST. – LT NORTH CENTRAL MOTORS DRIVEWAY	26
20+24 TO 20+68	BALTIMORE ST. – RT JAKE’S AUTO MALL SOUTH DRIVEWAY	61
23+32 TO 23+72	BALTIMORE ST. – RT JAKE’S AUTO MALL NORTH DRIVEWAY	67
TOTAL		154

CONCRETE CURB & GUTTER DESIGN B612		BL
STATION TO STATION	LOCATION	LIN FT
9+38 TO 9+85	BALTIMORE ST. – RT	79
9+83	BALTIMORE ST. – LT NORTH CENTRAL MOTORS DRIVEWAY	17
10+13	BALTIMORE ST. – LT NORTH CENTRAL MOTORS DRIVEWAY	17
20+24	BALTIMORE ST. – RT JAKE’S AUTO MALL DRIVEWAY	18
20+68	BALTIMORE ST. – RT JAKE’S AUTO MALL DRIVEWAY	18
23+32	BALTIMORE ST. – RT JAKE’S AUTO MALL DRIVEWAY	19
23+72	BALTIMORE ST. – RT JAKE’S AUTO MALL DRIVEWAY	19
TOTAL		170

MODULAR BLOCK RETAINING WALL			BM
STATION	LOCATION	APPROX. HEIGHT (FT)	SQ. YD.
18+60 TO 18+75	BALTIMORE ST. – RT	0.9	2
18+75 TO 19+00	BALTIMORE ST. – RT	2.42	7
19+00 TO 19+25	BALTIMORE ST. – RT	2.33	6
19+25 TO 19+50	BALTIMORE ST. – RT	2.19	6
19+50 TO 19+75	BALTIMORE ST. – RT	1.93	5
19+75 TO 20+00	BALTIMORE ST. – RT	1.55	4
20+00 TO 20+25	BALTIMORE ST. – RT	1.44	4
SOUTH DRIVEWAY WING 1	BALTIMORE ST. – RT	1.44	3
SOUTH DRIVEWAY WING 2	BALTIMORE ST. – RT	1.55	3
20+75 TO 21+00	BALTIMORE ST. – RT	1.55	4
21+00 TO 21+25	BALTIMORE ST. – RT	1.53	4
21+25 TO 21+50	BALTIMORE ST. – RT	1.36	4
21+50 TO 21+75	BALTIMORE ST. – RT	1.25	3
21+75 TO 22+00	BALTIMORE ST. – RT	1.27	4
22+00 TO 22+25	BALTIMORE ST. – RT	1.39	4
22+25 TO 22+50	BALTIMORE ST. – RT	1.23	3
22+50 TO 22+75	BALTIMORE ST. – RT	1.18	3
22+75 TO 23+00	BALTIMORE ST. – RT	1.23	3
23+00 TO 23+25	BALTIMORE ST. – RT	1.3	4
NORTH DRIVEWAY WING 1	BALTIMORE ST. – RT	1.28	3
TOTAL			80

SIGN PANELS TYPE C							BN
SIGN NO.	NOTE	TOTAL QTY.	POST	PANEL			PANEL LEGEND
				SIZE (IN)	AREA (SQ. FT.)	TOTAL AREA (SQ. FT.)	
C–2	8	2	SINGLE	VARIES X 8			D3–1 STREET
C–3		10	SINGLE	24 X 24	4	40	R8–3 NO PARKING
C–4		4	SINGLE	30 X 30	6	24	W1–4 REVERSE CURVE
C–6		1	SINGLE	24 X 30	5	5	R2–1 SPEED LIMIT 30 M.P.H
TOTAL						69	

INSTALL SALVAGED SIGNS						BV
SIGN NO.	NOTE	TOTAL QTY.	POST	PANEL	CODE NO.	PANEL LEGEND
				SIZE (IN)		
C–1		1	SINGLE	30 X 30	R1–1	STOP (SALVAGED)
C–5		1	TRIPLE	48 X 48	W3–3	SIGNAL AHEAD (SALVAGED)
TOTAL		2				

CONCRETE CURB & GUTTER DESIGN B618		BO
STATION TO STATION	LOCATION	LIN FT
9+37 TO 34+11	BALTIMORE ST. TO CHISHOLM ST. – LT	2,478
10+15 TO 34+11	BALTIMORE ST. TO CHISHOLM ST. – RT	2,422
TOTAL		4,900

SILT FENCE		BQ
STATION TO STATION	LOCATION	LIN. FT.
50+67 TO 52+96	171ST AVE.	229
9+16 TO 9+82	BALTIMORE ST. – RT	103
10+24 TO 15+10	BALTIMORE ST. – RT	572
11+28 TO 21+29	BALTIMORE ST. – LT	1,081
16+50	POND 1	1,297
25+00	POND 2	359
25+80	MNDOT DITCH	36
26+77 TO 30+47	173RD LANE – LT	442
28+28 TO 29+54	173RD LANE – RT	146
29+67	ENDANGERED PLANT PROTECTION	80
31+00	POND 3	392
31+50	POND 4	1,306
32+00 TO 35+09	CHISHOLM ST. – RT	373
32+19 TO 34+22	CHISHOLM ST. – LT	205
TOTAL		6,621

RIPRAP CLASS 3		BH
STATION	LOCATION	CU. YD.
16+59	BALTIMORE ST. – RT	16
	POND 1 OUTLET	13
19+41	BALTIMORE ST. – LT	7
21+71	BALTIMORE ST. – LT	5
24+16	BALTIMORE ST. – RT	7
25+29	BALTIMORE ST. – LT	6
30+30	173RD LANE – RT	10
30+93	CHISHOLM ST. – LT	6
31+54	CHISHOLM ST. – LT	10
	POND 4 OUTLET	6
TOTAL		86

NOTES:

- TOP OF GRADING SUBGRADE IS DEFINED AS THE BOTTOM OF THE CLASS 5 AGGREGATE BASE.
- BITUMINOUS AND CONCRETE DISTURBED BY CONSTRUCTION SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF OFFSITE IN ACCORDANCE WITH MnDOT SPEC. 2104.3C3.
- COMPACTION OF ALL GRADING AND BASE ITEMS SHALL BE BY THE "QUALITY COMPACTION METHOD".
- USE TACK COAT BETWEEN ALL BITUMINOUS LAYERS AND BETWEEN BITUMINOUS AND CONCRETE CURB AND GUTTER. TACK COAT IS INCIDENTAL.
- STRIP ALL TOPSOIL AREAS TO BE DISTURBED BY CONSTRUCTION AND REUSE TOPSOIL OR USE AS FILL OUTSIDE OF ROAD CORE.
- WHENEVER THE WORD "INCIDENTAL" IS USED IN THIS PLAN, IT SHALL MEAN THIS WORK SHALL BE INCIDENTAL FOR WHICH NO DIRECT COMPENSATION WILL BE MADE.
- STATIONING FOR LOCATION OF EXISTING AND NEW SIGNS IS APPROXIMATE.
- SIGN AND POST INSTALLED BY OTHERS

STORM DRAIN INLET PROTECTION		BR
STATION	LOCATION	QUANTITY
9+73	BALTIMORE ST. – LT	1
9+78	BALTIMORE ST. – RT	1
10+22	BALTIMORE ST. – RT	1
13+08	BALTIMORE ST. – RT	1
13+08	BALTIMORE ST. – LT	1
14+58	BALTIMORE ST. – RT	1
14+58	BALTIMORE ST. – LT	1
16+63	BALTIMORE ST. – RT	1
16+63	BALTIMORE ST. – LT	1
18+04	BALTIMORE ST. – RT	1
18+04	BALTIMORE ST. – LT	1
19+41	BALTIMORE ST. – RT	1
19+41	BALTIMORE ST. – LT	1
21+71	BALTIMORE ST. – RT	1
21+71	BALTIMORE ST. – LT	1
22+82	BALTIMORE ST. – LT	1
22+94	BALTIMORE ST. – RT	1
23+90	BALTIMORE ST. – RT	1
23+90	BALTIMORE ST. – LT	1
26+74	173RD LANE – RT	1
26+74	173RD LANE – LT	1
29+73	173RD LANE – RT	1
29+73	173RD LANE – LT	1
31+54	CHISHOLM ST. – RT	1
31+54	CHISHOLM ST. – LT	1
TOTAL		25

CULVERT END CONTROL		BS
STATION	LOCATION	QUANTITY
9+73	BALTIMORE ST. – LT	1
9+68	BALTIMORE ST. – RT	1
12+04	BALTIMORE ST. – RT	1
12+40	BALTIMORE ST. – LT	1
16+59	BALTIMORE ST. – RT	1
	POND 1 OUTLET	2
19+41	BALTIMORE ST. – LT	1
21+24	BALTIMORE ST. – LT	1
21+71	BALTIMORE ST. – LT	1
24+16	BALTIMORE ST. – RT	1
25+28	BALTIMORE ST. – RT	1
25+29	BALTIMORE ST. – LT	1
30+30	173RD LANE – RT	1
30+91	CHISHOLM ST. – RT	1
30+93	CHISHOLM ST. – LT	1
31+35	CHISHOLM ST. – RT	1
31+54	CHISHOLM ST. – LT	1
	POND 4 OUTLET	2
TOTAL		20

GEOTEXTILE FABRIC TYPE 4		BT
STATION	LOCATION	SQ. YD.
16+59	BALTIMORE ST. – RT	53
	POND 1 OUTLET	43
19+41	BALTIMORE ST. – RT	26
21+71	BALTIMORE ST. – LT	21
24+16	BALTIMORE ST. – RT	26
25+29	BALTIMORE ST. – LT	26
30+30	173RD LANE – RT	34
30+93	CHISHOLM ST. – LT	26
31+54	CHISHOLM ST. – LT	34
	POND 4 OUTLET	26
TOTAL		315



800-252-1166 651-454-0002

UTILITIES: CENTURYLINK (763) 712–5017  
CENTERPOINT ENERGY (763) 323–2760  
COMCAST (952) 607–4078  
CONNEXUS ENERGY (763) 323–4268  
XCEL ENERGY (612) 526–4508

DATE	REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.  
*Dave Krueger*  
DATE 05/29/25 REG. NO. 48768

**RFC ENGINEERING, INC.**  
**Consulting Engineers**

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763–862–8000  
Fax 763–862–8042

DESIGN BY: LDZ

S.A.P. 197–119–003 S.P. 0208–170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64’ SOUTH 171ST AVE TO 334’ SOUTH CROSSTOWN BLVD  
EARTHWORK SUMMARY AND TABULATIONS

DRAWN BY: LDZ

CHECKED BY: DAK

DWG: 2111 TAB 2

DATE: 05/29/25

JOB NUMBER: 2111

SHEET: 4 OF 43

FILE: 33–2–104



UTILITY COMPANIES – CA
GOPHER STATE ONE CALL FIELD UTILITY LOCATE REQUEST
CENTERPOINT ENERGY
CENTURYLINK
CONNEXUS ENERGY
COMCAST CABLE COMMUNICATIONS, INC.
MINNESOTA DEPARTMENT OF TRANSPORTATION
ZAYO BANDWITDTH

CENTERPOINT ENERGY				CB
ALIGNMENT	STATION	OFFSET	INPLACE ITEM	NOTES
BALTIMORE STREET	10+00.00 TO 18+29.03	VAREIS	BURIED GAS	LEAVE AS IS
BALTIMORE STREET	18+29.03 TO 26+22.32	VARIES	BURIED GAS	LEAVE AS IS
173RD LANE & CHISHOLM STREET	26+22.30 TO 34+08.46	VAREIS	BURIED GAS	LEAVE AS IS

CONNEXUS ENERGY				CD
ALIGNMENT	STATION	OFFSET	INPLACE ITEM	NOTES
BALTIMORE STREET	10+00.00 TO 18+29.03	VAREIS	OVERHEAD ELECTRIC	LEAVE AS IS
BALTIMORE STREET	18+29.03 TO 26+22.32	33' LT	OVERHEAD ELECTRIC	LEAVE AS IS
173RD LANE & CHISHOLM STREET	26+22.30 TO 34+08.46	VAREIS	OVERHEAD ELECTRIC	LEAVE AS IS

MINNESOTA DOT				CF
ALIGNMENT	STATION	OFFSET	INPLACE ITEM	NOTES
BALTIMORE STREET	10+00.00 TO 18+29.03	VARIES	BURIED CABLE	LEAVE AS IS
BALTIMORE STREET	18+29.03 TO 26+22.32	50' LT TO 74' LT	BURIED CABLE	LEAVE AS IS
173RD LANE & CHISHOLM STREET	26+22.30 TO 34+08.46	VARIES	BURIED CABLE	LEAVE AS IS


GENERAL NOTES

1. STATIONING FOR BALTIMORE STREET REFERENCES THE PROPOSED CENTERLINE FOR THE PROJECT.
2. PRIOR TO REMOVING THE MNDOT STREET LIGHT, ELECTRIC CABINET, AND UNDERGROUND ELECTRIC, NOTIFY PAUL BABIN WITH MNDOT METRO LIGHTING DESIGN (651)234-7873.
3. ALL REMOVALS AND RELOCATIONS, EXCEPT FOR MNDOT FACILITIES, ARE TO BE COMPLETED BY THE UTILITY OWNER.

CENTURY LINK				CC
ALIGNMENT	STATION	OFFSET	INPLACE ITEM	NOTES
BALTIMORE STREET	10+00.00 TO 18+29.03	VAREIS	BURIED CABLE	LEAVE AS IS
BALTIMORE STREET	18+29.03 TO 26+22.32	VARIES	BURIED CABLE	LEAVE AS IS
173RD LANE & CHISHOLM STREET	26+22.30 TO 34+08.46	VAREIS	BURIED CABLE	LEAVE AS IS

COMCAST				CE
ALIGNMENT	STATION	OFFSET	INPLACE ITEM	NOTES
BALTIMORE STREET	10+00.00 TO 18+29.03	VAREIS	BURIED CABLE	LEAVE AS IS
BALTIMORE STREET	18+29.03 TO 26+22.32	VARIES	BURIED CABLE	LEAVE AS IS
173RD LANE & CHISHOLM STREET	26+22.30 TO 34+08.46	VAREIS	BURIED CABLE	LEAVE AS IS


ZAYO BANDWIDTH				CG
ALIGNMENT	STATION	OFFSET	INPLACE ITEM	NOTES
BALTIMORE STREET	10+00.00 TO 18+29.03	VARIES	BURIED CABLE	LEAVE AS IS
BALTIMORE STREET	18+29.03 TO 26+22.32	50' LT TO 74' LT	BURIED CABLE	LEAVE AS IS
173RD LANE & CHISHOLM STREET	26+22.30 TO 34+08.46	VARIES	BURIED CABLE	LEAVE AS IS



TYPICAL URBAN SECTION

TYPICAL STREET SECTION  
COMMERCIAL 9-TON RFC-366B1


NOT TO SCALE



TYPICAL URBAN SECTION


WHERE ORGANIC MATERIAL COMPLETELY REMOVED

TYP. SUBGRADE EXCAVATION RFC-365A1  
NOT TO SCALE



COMMERCIAL DRIVEWAY DETAIL RFC-370A1


NOT TO SCALE



1. Remove organic material to a minimum of 4 feet and place the Geotextile Fabric and install select grading material or other approved material. No vehicle traffic is allowed directly on Geotextile Fabric.
2. Furnish and install Geotextile Fabric Type 5 to 12" past removal limits. Disturbance of existing terrain where Fabric is to be placed shall be minimized.


TYPICAL FLOATING ROAD SECTION  
NEW ROAD CONSTRUCTION RFC-365C4

NOT TO SCALE




FORESLOPE DETAIL RFC-856A  
NOT TO SCALE

CURB END DETAIL RFC-380A  
NOT TO SCALE



TYPICAL DITCH DETAIL RFC-856B  
NOT TO SCALE



- SEQUENCING:
1. Place silt fence along construction limits, the portion of silt fence in front of the pipe shall be removed during flared end section placement.
  2. Once the flared end section is placed, silt fence shall be furnished and installed around the top of the flared end section and surrounding the riprap.
  3. Any additional outlet protection shall be added as required.
  4. Contractor may substitute silt fence for bio-roll or rock log to act as weir for flow into culvert.

SILT FENCE AT FES RFC-857  
NOT TO SCALE



UTILITIES: CENTURYLINK (763) 712-5017  
CENTERPOINT ENERGY (763) 323-2760  
COMCAST (952) 607-4078  
CONNEXUS ENERGY (763) 323-4268  
XCEL ENERGY (612) 526-4508

DATE	REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.  
*Dave Krueger*  
DATE 05/29/25 REG. NO. 48768


**RFC ENGINEERING, INC.**  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
TYPICAL SECTION AND DETAILS

DESIGN BY: LDZ DRAWN BY: LDZ CHECKED BY: DAK

DWG: 2111 DETAIL 1  
DATE: 05/29/25  
JOB NUMBER: 2111  
SHEET: 6 OF 43  
FILE: 33-2-106




#### CONSTRUCTION SEQUENCE

1. LOOSELY PLACE 6" OF FINE AGGREGATE BEDDING MATERIAL TO GRADE. DO NOT COMPACT PRIOR TO PIPE PLACEMENT.
2. FOR PIPES WITH BELL, REMOVE MATERIAL IN BELL AREA PRIOR TO PLACEMENT.
3. FURNISH AND INSTALL PIPE TO GRADE.
4. AFTER PLACEMENT OF THE PIPE, PLACE ADDITIONAL BEDDING AND COMPACT THE FULL LENGTH ON BOTH SIDES OF THE PIPE UNDERNEATH THE HAUNCH AREA BY FIRST SHOVEL SLIDING (MANUALLY SHOVE THE BLADE END OF SHOVEL AT AN ANGLE DOWN THE ENTIRE LENGTH OF THE HAUNCH UNDER THE PIPE) THEN COMPACT THE HAUNCH AT AN ANGLE USING A POWERED MECHANICAL OR PNEUMATIC DEVICE (I.E. POLE TAMPER, JUMPING JACK, OR SIMILAR). COMPACT THE REMAINING MATERIAL OUTSIDE THE HAUNCH AREA TO THE REQUIREMENTS OF THE APPLICABLE MATERIAL TYPE ENSURING THAT THE ENTIRE LENGTH OF PIPE IS SUPPORTED UNIFORMLY BY BEDDING.
5. PLACE AND COMPACT BACKFILL EVENLY AND SIMULTANEOUSLY IN 6" LIFTS ON EACH SIDE OF THE PIPE UP TO THE MID-HEIGHT WHEN COMPACTED.
6. COMPLETE REMAINING BACKFILL.

#### NOTES

EXCAVATE & CONSTRUCT ALL TRENCHES AND SLOPES PER OSHA REQUIREMENTS. PIPE SIZE IS BASED ON THE NOMINAL INSIDE DIAMETER. PROTECT ALL PIPE DURING CONSTRUCTION PER SPEC. 2501 OR 2503.




#### CONSTRUCTION SEQUENCE

1. LOOSELY PLACE 6" OF FINE AGGREGATE BEDDING MATERIAL TO GRADE. DO NOT COMPACT PRIOR TO PIPE PLACEMENT.
2. FOR PIPES WITH BELL, REMOVE MATERIAL IN BELL AREA PRIOR TO PLACEMENT.
3. FURNISH AND INSTALL PIPE TO GRADE.
4. AFTER PLACEMENT OF THE PIPE, PLACE ADDITIONAL BEDDING AND COMPACT THE FULL LENGTH ON BOTH SIDES OF THE PIPE UNDERNEATH THE HAUNCH AREA BY FIRST SHOVEL SLIDING (MANUALLY SHOVE THE BLADE END OF SHOVEL AT AN ANGLE DOWN THE ENTIRE LENGTH OF THE HAUNCH UNDER THE PIPE) THEN COMPACT THE HAUNCH AT AN ANGLE USING A POWERED MECHANICAL OR PNEUMATIC DEVICE (I.E. POLE TAMPER, JUMPING JACK, OR SIMILAR). COMPACT THE REMAINING MATERIAL OUTSIDE THE HAUNCH AREA TO THE REQUIREMENTS OF THE APPLICABLE MATERIAL TYPE ENSURING THAT THE ENTIRE LENGTH OF PIPE IS SUPPORTED UNIFORMLY BY BEDDING.
5. PLACE AND COMPACT BACKFILL EVENLY AND SIMULTANEOUSLY IN 6" LIFTS ON EACH SIDE OF THE PIPE UP TO THE MID-HEIGHT WHEN COMPACTED.
6. COMPLETE REMAINING BACKFILL.

#### NOTES

EXCAVATE & CONSTRUCT ALL TRENCHES AND SLOPES PER OSHA REQUIREMENTS. PIPE SIZE IS BASED ON THE NOMINAL INSIDE DIAMETER. PROTECT ALL PIPE DURING CONSTRUCTION PER SPEC. 2501 OR 2503.




SEAL FABRIC ONTO CATCH BASIN AND CATCH BASIN MANHOLE WITH DUCT TAPE. OVER LAP ALL SEAMS. 12" MIN.

#### SECTIONAL VIEW

#### FABRIC AROUND CATCH BASIN RFC-463

NOT TO SCALE




#### CPP TRASH GUARD RFC-466C

NOT TO SCALE

#### STORM DRAIN BEDDING FOR RIGID AND FLEXIBLE PIPE RFC-654


NOT TO SCALE

NOTE: HS20 Roadway Loading Catch Basin Cover Slab of Precast Reinforced Concrete with Rectangular Opening.



#### Note:


1. Steps needed for structure height greater than 4'.
2. Cover Slab to Rest on Bed of Mortar on Full Thickness of Structure Walls, not to Rest on Pipe Tongue or Groove.
3. Location of Structure as Shown in Plans.
4. See Plan for Box and Grate Type.




#### RECTANGULAR INLET FOR ROUND MANHOLE RFC-465A3

NOT TO SCALE

SPECIAL 4 = 60" Ø  
SPECIAL 5 = 72" Ø  
SPECIAL 6 = 96" Ø



#### CATCH BASIN PLAN



#### SECTION A-A


- NOTE:
1. 2 Min., 3 Max. Adjustment Rings
  2. Stagger on the adjustment rings not to exceed 3/4 inch total.

#### RECTANGULAR CATCH BASIN RFC-459C

NOT TO SCALE


SPECIAL

NOTE: HS20 Roadway Loading Catch Basin Cover Slab of Precast Reinforced Concrete with Rectangular Opening.



#### Note:


1. Steps needed for structure height greater than 4'.
2. Cover Slab to Rest on Bed of Mortar on Full Thickness of Structure Walls, not to Rest on Pipe Tongue or Groove.
3. Location of Structure as Shown in Plans.
4. See Plan for Box and Grate Type.




#### RECTANGULAR INLET FOR ROUND MANHOLE RFC-465A1

NOT TO SCALE

SPECIAL 1 = 48" Ø  
SPECIAL 2 = 60" Ø  
SPECIAL 3 = 84" Ø



#### PLAN



#### ELEVATION


#### Note:

- 1.) Trash guard to be galvanized after fabrication
- 2.) The size of each trash guard will vary to fit the apron size.
- 3.) All bolts to be non-rusting stainless steel.
- 4.) Weld all bolts to prevent entry after final storm sewer cleaning.
- 5.) Round all steel bars such that ends are smooth and free of burs.

#### FOR PIPE DIAMETERS 30" AND SMALLER

#### RCP TRASH GUARD RFC-466B


NOT TO SCALE



BAFFLE WEIR ELEVATIONS					
	POND 1	POND 2	FES 51 POND 3	FES 63 POND 3	POND 4
A	905.30	905.00	906.80	905.50	905.00
B	904.30	904.00	904.50	904.50	904.00
C	904.80	904.50	905.00	905.00	904.50
D	907.20	906.60	907.30	907.30	906.40
E	22"X22"	12"X12"	6"X6"	18"X18"	18"X18"
F	905.20	905.00	906.00	SEE PROFILE ON SHEET 29	904.50
G	8'	8'	8'	8'	8'
*H	908.20	906.90	907.50	907.50	906.50

\* BAFFLE WEIRS TO BE CONSTRUCTED AT HIGH WATER LEVELS LISTED IN ROW H INSTEAD OF ROW D TO ACCOUNT FOR FUTURE SITE DEVELOPMENT


POND OUTLET BAFFLE RFC-850B2  
NOT TO SCALE




0.6% minimum longitudinal slope along trench drain.

TRENCH DRAIN DETAIL RFC-472B  
NOT TO SCALE


TRENCH DRAIN OUTLET ELEVATIONS		
	STUB 75	STUB 6
A	24	24
B	10	10
C	906.65	905.87
D	906.59	905.68



ROUND MANHOLE RFC-465C  
NOT TO SCALE  
SPECIAL 7 = 48" Ø




TRANSITION CURB: D412M TO B618  
RFC-356A10  
NOT TO SCALE




TRANSITION FOR D412 TO B612 CURB & GUTTER AT CURB RETURNS

TRANSITION CURB: D412 TO B612 RFC-356A4  
NOT TO SCALE




TRANSITION FOR D312 TO B618 CURB & GUTTER AT CURB RETURNS

TRANSITION CURB: D312M TO B618 RFC-356A2  
NOT TO SCALE




TRANSITION CURB: B612 TO B618 RFC-356B  
NOT TO SCALE




**FILTER BAG INSERT ③**

(CAN BE INSTALLED IN ANY INLET TYPE  
WITH OR WITHOUT A CURB BOX)




**SEDIMENT CONTROL INLET HAT**


NOTE:  
THE SEDIMENT CONTROL BARRIER SHALL BE A METAL  
OR PLASTIC/POLYETHYLENE RISER SIZED TO FIT INSIDE  
THE CATCH BASIN/MANHOLE; HAVE PERFORATIONS TO ALLOW  
FOR WATER INFILTRATION; HAVE AN OVERFLOW OPENING,  
FLANGES AND A LID/COVER.




**ROCK LOG/COMPOST LOG**




**TUBE RISER**



**SECTION  
(UP POSITION)**




**PERSPECTIVE VIEW**



**SECTION  
(DOWN POSITION)**

**POP-UP HEAD**



**SILT FENCE RING AND ROCK FILTER BERM**  
USE WHERE INLET DRAINS IN AN AREA WITH SLOPES AT 1:3 OR LESS

**NOTES:**

SEE SPECS. 2573, 3137, & 3886.

DEVICES MUST BE ADJUSTED ACCORDINGLY AS TO NOT CAUSE FLOODING ON ROADWAY  
THAT WOULD IMPEED TRAFFIC FLOW.

- ① ALL GEOTEXTILE USED FOR INLET PROTECTION SHALL BE MONOFILAMENT IN BOTH  
DIRECTIONS, MEETING SPEC. 3886.
- ② FINISHED SIZE, INCLUDING POCKETS WHERE REQUIRED SHALL EXTEND A MINIMUM OF  
10 INCHES AROUND THE PERIMETER TO FACILITATE MAINTENANCE OR REMOVAL.
- ③ INSTALLATION NOTES:  
DO NOT PLACE FILTER BAG INSERT IN INLETS SHALLOWER THAN 30 INCHES,  
MEASURED FROM THE BOTTOM OF THE INLET TO THE TOP OF THE GRATE. THE  
PLACED BAG SHALL HAVE A MINIMUM SIDE CLEARANCE OF 3 INCHES BETWEEN  
THE INLET WALLS AND THE BAG, MEASURED AT THE BOTTOM OF THE OVERFLOW HOLES.  
WHERE NECESSARY THE CONTRACTOR SHALL CLINCH THE BAG, USING PLASTIC ZIP TIES,  
TO ACHIEVE THE 3 INCH SIDE CLEARANCE.
- ④ FLAP POCKETS SHALL BE LARGE ENOUGH TO ACCEPT WOOD 2 INCH X 4 INCH OR USE A  
ROCK SOCK OR SAND BAGS IN PLACE OF THE FLAP POCKETS.
- ⑤ SOCK HEIGHT MUST NOT BE SO HIGH AS TO SLOW DOWN WATER FILTRATION TO CAUSE  
FLOODING OF THE ROADWAY.
- ⑥ GEOTEXTILE SOCK BETWEEN 4-10 FEET LONG AND 4-6 INCH DIAMETER. SEAM TO BE  
JOINED BY TWO ROWS OF STITCHING WITH A PLASTIC MESH BACKING OR PROVIDE A  
HEAT BONDED SEAM (OR APPROVED EQUIVALENT). FILL ROCK LOG WITH OPEN GRADED  
AGGREGATE CONSISTING OF SOUND DURABLE PARTICLES OF COARSE AGGREGATE  
CONFORMING TO SPEC. 3137 TABLE 3137-1; CA-3 GRADATION.

REVISION:
APPROVED: 2-28-2017
<i>[Signature]</i> CHIEF ENVIRONMENTAL OFFICER



STANDARD PLAN 5-297.405 4 OF 8

*[Signature]*  
STATE DESIGN ENGINEER

APPROVED: 2-28-2017  
REVISED:


STATE PROJ. NO.

**TEMPORARY SEDIMENT CONTROL**


**STORM DRAIN INLET PROTECTION**

(T.H. ) SHEET NO. 9 OF 43 SHEETS







SLASH MULCH, CRUSHED ROCK, OR SHEET  
PAD CONSTRUCTION EXIT ⑤⑦




RUMBLE PAD  
CONSTRUCTION EXIT ⑤⑦



RUMBLE PAD



SHEET PAD



SLASH MULCH OR CRUSHED ROCK

#### NOTES:

SEE SPECS. 2573 & 3882.

- ① MINIMUM LENGTH SHALL BE THE GREATER OF 50 FEET OR A LENGTH SUFFICIENT TO ALLOW A MINIMUM OF 5 TIRE ROTATIONS ON THE PROVIDED PAD. MINIMUM LENGTH SHALL BE CALCULATED USING THE LARGEST TIRE WHICH WILL BE USED IN TYPICAL OPERATIONS.
- ② PROVIDE RADIUS OR WIDEN PAD SUFFICIENTLY TO PREVENT VEHICLE TIRES FROM TRACKING OFF OF PAD WHEN LEAVING SITE.
- ③ IF RUNOFF FROM DISTURBED AREAS FLOWS TOWARD CONSTRUCTION EXITS, PREVENT RUNOFF FROM DRAINING DIRECTLY TO PUBLIC ROAD OVER CONSTRUCTION EXIT BY CROWNING THE EXIT OR SLOPING TO ONE SIDE. IF SURFACE GRADING IS INSUFFICIENT, PROVIDE OTHER MEANS OF INTERCEPTING RUNOFF.
- ④ IF RUNOFF FROM CONSTRUCTION EXITS WILL DRAIN OFF OF PROJECT SITE, PROVIDE SEDIMENT TRAP WITH STABILIZED OVERFLOW.
- ⑤ IF A TIRE WASH OFF IS REQUIRED THE CONSTRUCTION EXITS SHALL BE GRADED TO DRAIN THE WASH WATER TO A SEDIMENT TRAP.
- ⑥ MINIMUM LENGTH OF RUMBLE PAD SHALL BE 20 FEET, OR AS REQUIRED TO REMOVE SEDIMENT FROM TIRES. IF SIGNIFICANT SEDIMENT IS TRACKED FROM THE SITE, THE RUMBLE PAD SHALL BE LENGTHENED OR THE DESIGN MODIFIED TO PROVIDE ADDITIONAL VIBRATION. WASH-OFF LENGTH SHALL BE AS REQUIRED TO EFFECTIVELY REMOVE CONSTRUCTION SEDIMENT FROM VEHICLE TIRES.
- ⑦ MAINTENANCE OF CONSTRUCTION EXITS SHALL OCCUR WHEN THE EFFECTIVENESS OF SEDIMENT REMOVAL HAS BEEN REDUCED. MAINTENANCE SHALL CONSIST OF REMOVING SEDIMENT AND CLEANING THE MATERIALS OR PLACING ADDITIONAL MATERIAL (SLASH MULCH OR CRUSHED ROCK) OVER SEDIMENT FILLED MATERIAL TO RESTORE EFFECTIVENESS.

REVISION:

APPROVED: 2-28-2017

*[Signature]*  
CHIEF ENVIRONMENTAL OFFICER



STANDARD PLAN 5-297.405

5 OF 8

*[Signature]*  
STATE DESIGN ENGINEER

APPROVED: 2-28-2017  
REVISED:


STATE PROJ. NO.

TEMPORARY SEDIMENT CONTROL


STABILIZED CONSTRUCTION EXIT

(T.H. )


SHEET NO. 10 OF 43 SHEETS




**SILT FENCE TYPE HI ②  
(HAND INSTALLED)**




**SILT FENCE TYPE MS ②  
(MACHINE SLICED)**




**SILT FENCE TYPE PA ③  
(PREASSEMBLED)**



**SILT FENCE ONLY ④**




**SILT FENCE WITH SAND BAGS ⑤**



**SILT FENCE WITH SHEETING ⑥**

**INSTALLATION AT BRIDGE EMBANKMENT ADJACENT TO WATER**



**PLAN VIEW**


**PERSPECTIVE VIEW**

**J-HOOK INSTALLATION**

**NOTES:**

SEE SPECS. 2573, 3149 & 3886.

- ① COARSE FILTER AGGREGATE (SPEC. 3149) SHALL BE INCIDENTAL.
- ② TO PROTECT AREAS FROM SHEET FLOW. MAXIMUM CONTRIBUTING AREA: 1 ACRE.
- ③ TO PROTECT AREAS FROM SHEET FLOW. MAXIMUM CONTRIBUTING AREA: 0.25 ACRE.
- ④ WATER COURSE FLOW VELOCITY: STANDING. CONTRIBUTING SLOPE AREA: 1/2 ACRE.
- ⑤ WATER COURSE FLOW VELOCITY: 1 TO 7 FT./SEC. CONTRIBUTING SLOPE AREA: 1 ACRE.
- ⑥ WATER COURSE FLOW VELOCITY: 8 TO 15 FT./SEC. CONTRIBUTING SLOPE AREA: 3 ACRES.



**LOCATION AT TOE OF ROADWAY EMBANKMENT**

REVISION:
APPROVED: 2-28-2017
CHIEF ENVIRONMENTAL OFFICER



STANDARD PLAN 5-297.405 6 OF 8

APPROVED: 2-28-2017  
REVISOR: Tom S. J. J.




STATE PROJ. NO.

**TEMPORARY SEDIMENT CONTROL**




**SILT FENCE**

(T.H. )


SHEET NO. 11 OF 43 SHEETS




CULVERT STANDPIPE INSERT (D-RISER)  
d = CULVERT SIZE: 12" - 36"



CULVERT STANDPIPE INSERT (D-RISER)



SEDIMENT CONTROL LOG WEIR  
(COMPOST, WOOD CHIP, OR ROCK)  
d = CULVERT SIZE: 12" - 36"



WOOD PLANK WEIR

#### NOTES:

SEE SPECS. 2573, 3891 & 3893.

FOR USE WHEN TEMPORARY PONDING IS NEEDED IN DITCH SECTIONS FOR SEDIMENT CONTROL.

MANUFACTURED ALTERNATIVES LISTED ON MnDOT'S APPROVED PRODUCTS LIST MAY BE SUBSTITUTED AT NO ADDITIONAL COST.

- ① ROCK LOG OR SANDBAG TO HOLD STANDPIPE AND ACT AS A SEAL BETWEEN RISER PIPE AND CULVERT.
- ② PLACE CULVERT APRON AND SLIDE TEMPORARY STANDPIPE INTO CSP OR RCP CULVERT.
- ③ ALL GEOTEXTILE USED FOR CULVERT PROTECTION SHALL BE MONOFILAMENT IN BOTH DIRECTIONS, MEETING SPEC. 3886 FOR MACHINE SLICED.
- ④ ROCK LOG OR RIP RAP TO HOLD STANDPIPE AND ACT AS A FILTER BETWEEN RISER PIPE AND CULVERT.
- ⑤ HEIGHT OVERFLOW NOT TO CAUSE FLOODING OF ROAD OR ADJACENT PROPERTIES.

REVISION:

APPROVED: 2-28-2017

CHIEF ENVIRONMENTAL OFFICER

**m**  
MINNESOTA  
DEPARTMENT  
OF  
TRANSPORTATION

STANDARD PLAN 5-297.405 8 OF 8

STATE DESIGN ENGINEER

APPROVED: 2-28-2017  
REVISED:

STATE PROJ. NO.

TEMPORARY SEDIMENT CONTROL

CULVERT END CONTROLS

(T.H. ) SHEET NO. 12 OF 43 SHEETS

### LOADING CASES

EQUIVALENT 2 FT. EARTH PRESSURE SURCHARGE

LEVEL FILL  
CASE 1

1:2 FILL SLOPE

1:2 SLOPED FILL  
CASE 2

1:3 FILL SLOPE

1:3 SLOPED FILL  
CASE 3

SAMPLE OF ESTIMATED QUANTITIES TABULATION FOR MODULAR BLOCK WALLS ③		
	UNIT	QUANTITY
STRUCTURE EXCAVATION CLASS ---	CU. YD.	
STRUCTURAL BACKFILL (CV)	CU. YD.	
STRUCTURAL CONCRETE (1P42)	CU. YD.	
COARSE FILTER AGGREGATE	CU. YD.	
MODULAR BLOCK RETAINING WALL	SQ. FT.	
TYPE 1 GEOTEXTILE	SQ. YD.	

- 

DEFINITION OF TERMS	
MBW =	MODULAR BLOCK WALL
C.I.P. =	CAST-IN-PLACE
H =	WALL HEIGHT FROM TOP OF CAP TO BOTTOM OF LOWERMOST BLOCK UNIT
S =	VERTICAL REINFORCEMENT SPACING
REINFORCEMENT COVERAGE RATIO	WIDTH OF SOIL REINFORCEMENTS TO HORIZONTAL SPACING (100% COVERAGE RATIO REQUIRED)

NOTES TO CONTRACTOR:

APPROVED COMBINATIONS OF MODULAR BLOCK UNIT AND SOIL REINFORCEMENT AND APPROVED MODULAR BLOCK UNIT PRODUCTS ARE MAINTAINED BY THE FOUNDATION UNIT (GEOTECHNICAL ENGINEERING SECTION), AND ARE POSTED AT <https://www.dot.state.mn.us> ONLY APPROVED PRODUCT COMBINATIONS AND APPROVED BLOCK UNITS PRODUCED FROM APPROVED SOURCES SHALL BE USED.

PROVIDE DETAILED SHOP DRAWINGS FOR CONSTRUCTION CONTAINING:

- A COPY OF MnDOT STANDARD SHEETS FOR LOADING CASE(S) USED WITH BLOCK TYPE AND SPACING NOTED ON THE "MODULAR BLOCK WALL REINFORCEMENT LAYOUT" TABLE.
- ELEVATION VIEW WITH REINFORCEMENT PLACEMENT REQUIREMENTS, WALL FACING LAYOUT, AND GEOMETRIC INFORMATION. TOP OF WALL MAY EXTEND UP TO 4" ABOVE PLAN TOP OF WALL ELEVATION.
- PLAN VIEW WITH BOTTOM AND TOP OF WALL ALIGNMENT, AND PLAN LIMITS OF WALL ALIGNMENT.
- CROSS SECTIONS DETAILING BATTER, REINFORCEMENT, VERTICAL SPACING, REINFORCEMENT LENGTHS, SUBSURFACE DRAINAGE, SURFACE DRAINAGE, AND WATER RUNOFF COLLECTION ABOVE WALL.
- REINFORCEMENT LAYOUT: REINFORCEMENT SHALL BE PLACED AT 100% COVERAGE RATIO. REINFORCEMENT ELEVATIONS SHALL BE CONSISTENT ACROSS LENGTH OF WALL STRUCTURE.
- BLOCK, REINFORCEMENT AND FILL PLACEMENT METHODS AND REQUIREMENTS.
- DETAIL ALL WALL FILL PENETRATIONS AND WALL FACE PENETRATIONS. DETAIL REINFORCEMENT AND/OR WALL FACING UNIT PLACEMENT AROUND PENETRATIONS. VERTICAL PENETRATIONS GREATER THAN 1 FT. DIAMETER REQUIRE A STRUCTURAL GEGRID DIVERSION SYSTEM AND/OR PREINSTALLED SLEEVES.
- DETAILS THAT ARE SPECIFIC TO VENDOR PRODUCTS AND THEIR INTERACTION WITH OTHER PROJECT COMPONENTS.
- LIST INFORMATION ON APPROVED COMBINATION OF MBW UNIT AND GEOSYNTHETIC REINFORCEMENT, INCLUDING MnDOT CLASSIFICATION CODE, NOMINAL BLOCK WIDTH, PROPERTIES FOR FIELD IDENTIFICATION, AND INSTALLATION INSTRUCTIONS.
- DETAILS OF CAP UNITS AND INSTALLATION/FASTENING INSTRUCTIONS FOR THE CAPS. CAP UNITS SHALL BE SET IN A BED OF ADHESIVE DESIGNED TO WITHSTAND MOISTURE AND TEMPERATURE EXTREMES, REMAIN FLEXIBLE, AND SHALL BE SPECIFICALLY FORMULATED FOR BONDING MASONRY TO MASONRY.
- CERTIFICATION BY PROFESSIONAL ENGINEER EXPERIENCED IN MBW DESIGN THAT THE CONSTRUCTION LAYOUT MEETS THE REQUIREMENTS OF PLANS AND MnDOT MBW STANDARDS. DEVIATION FROM STANDARD DESIGN TABLES ARE PERMITTED BY VALUE ENGINEERING SUBMITTAL ONLY ON PROJECTS WITH OVER 5000 SQ. FT. OF WALL.
- CONTRACTOR MUST PROVIDE AN MBW SUBMITTAL THAT DETAILS EROSION PREVENTION AND PERMANENT PLANT STABILIZATION. THE SUBMITTAL MUST ALSO MEET THE REQUIREMENTS OF SPEC. 1712.2.

## DESIGN CRITERIA

---

DESIGN CRITERIA FOLLOWS THE "AASHTO LRFD BRIDGE DESIGN SPECIFICATION" (7TH EDITION, 2014) EXCEPT FOR THE DEVIATIONS NOTED BELOW. DESIGN CRITERIA ARE IN ACCORDANCE WITH MnDOT POLICY, AS RECORDED IN THE MnDOT ROAD DESIGN MANUAL, OR FACILITY DESIGN GUIDE.

- A. THE MINIMUM REINFORCEMENT LENGTH IS 7 FT. FROM THE FRONT OF THE BLOCK OR  $0.8H$  FOR CASE 1 AND CASE 3 AND  $1.2H$  FOR CASE 2, WHICHEVER IS GREATER.
- B. THE REINFORCEMENT FILL FRICTION ANGLE IS  $34^\circ$ .
- C. THE LATERAL EARTH PRESSURE COMPUTATION FOR EXTERNAL STABILITY CALCULATIONS USES AN INTERFACE FRICTION ANGLE SET EQUAL TO THE RETAINED BACKFILL ANGLE.
- D. THE LATERAL EARTH PRESSURE COMPUTATION FOR INTERNAL STABILITY CALCULATIONS USES THE EFFECTS OF WALL FACE BATTER.

LOAD FACTORS - STRENGTH LIMIT STATE

HORIZONTAL EARTH PRESSURE ( $\gamma_{EH}$ ) = 1.5 FOR EXTERNAL STABILITY  
HORIZONTAL EARTH PRESSURE ( $\gamma_{EH}$ ) = 1.35 FOR INTERNAL STABILITY  
VERTICAL PRESSURE FROM DEAD LOAD OF EARTH FILL ( $\gamma_{EV}$ ) = 1.35 FOR BEARING CAPACITY  
VERTICAL PRESSURE FROM DEAD LOAD OF EARTH FILL ( $\gamma_{EV}$ ) = 1.0 FOR SLIDING AND PULL OUT  
EQUIVALENT EARTH PRESSURE SURCHARGE ( $\gamma$ ) = 1.35

RESISTANCE FACTORS - STRENGTH LIMIT STATE

BEARING  $\phi_{BR}$  = 0.65  
DIRECT SLIDING  $\phi_{DS}$  = 1.0  
GEOGRID STRENGTH  $\phi$  = 0.9  
GEOGRID BLOCK CONNECTION STRENGTH  $\phi$  = 0.9  
GEOGRID PULLOUT  $\phi$  = 0.9

SEE FOUNDATION REPORT FOR NOMINAL SOIL BEARING RESISTANCE OF FOUNDATION SOIL.

CASE 1 AND 3 - NOMINAL SOIL BEARING RESISTANCE OF 2000 PSF IS REQUIRED FOR WALLS UP TO 12 FT IN HEIGHT. FOR WALLS GREATER THAN 12 FT IN HEIGHT, THE REQUIRED NOMINAL BEARING RESISTANCE IS EQUAL TO  $2000 \text{ PSF} + (H-10)(1500 \text{ PSF})$  WHERE H IS IN FEET.

CASE 2 - NOMINAL SOIL BEARING RESISTANCE OF 2500 PSF IS REQUIRED FOR WALLS UP TO 12 FT IN HEIGHT. FOR WALLS GREATER THAN 12 FT IN HEIGHT, THE REQUIRED NOMINAL BEARING RESISTANCE IS EQUAL TO  $2500 \text{ PSF} + (H-10)(2200 \text{ PSF})$  WHERE H IS IN FEET.

REINFORCED WALL FILL CHARACTERISTICS:

- A. USE STRUCTURAL BACKFILL (SPEC. 3149.2D2)
- B. INTERNAL ANGLE OF FRICTION ( $\phi_r$ ) =  $34^\circ$  MINIMUM
- C. COHESION (C) = 0
- D. MOIST UNIT WEIGHT ( $\gamma_r$ ) = 125 PCF

COARSE FILTER AGGREGATE CHARACTERISTICS:

- A. COARSE FILTER AGGREGATE TO MEET SPEC. 3149.2H.

RETAINED BACKFILL CHARACTERISTICS:

- A. INTERNAL ANGLE OF FRICTION ( $\phi_b$ ) =  $30^\circ$
- B. COHESION (C) = 0
- C. MOIST UNIT WEIGHT ( $\gamma_b$ ) = 120 PCF

FOUNDATION SOILS CHARACTERISTICS:

- A. INTERNAL ANGLE OF FRICTION ( $\phi_f$ ) =  $30^\circ$
- B. COHESION (C) = 0
- C. UNIT WEIGHT ( $\gamma_f$ ) = 120 PCF

**BASIS OF DESIGN:**

IN ADDITION TO THE STANDARD SHEETS, INCLUDE PLAN AND FRONT ELEVATION VIEWS OF THE MODULAR BLOCK RETAINING WALLS IN THE PLANS. THE PLAN VIEW MUST SHOW ALIGNMENT BASELINE, LIMITS OF BOTTOM OF WALL ALIGNMENT, AND LIMITS OF TOP OF WALL ALIGNMENT AS ALIGNMENTS VARY WITH BATTER OF WALL SYSTEM ACTUALLY SUPPLIED. THE FRONT ELEVATION MUST IDENTIFY BOTTOM AND TOP OF WALL ELEVATIONS, EXISTING GRADES, AND FINISHED GRADES.

IF THE WALL IS CURVED, THE RADIUS AT THE BOTTOM AND THE TOP OF EACH WALL SEGMENT AND THE P.C. AND P.T. STATION POINTS OFF OF BASELINE AND LIMITS OF BOTTOM AND TOP OF WALL ALIGNMENT MUST BE SHOWN.

REFERENCE STANDARD PLATES AND PROVIDE DETAILS FOR TRAFFIC BARRIERS, CURE AND GUTTER, HANDRAILS AND FENCING AS REQUIRED BY PROJECT CONDITIONS. SEE AASHTO MANUALS, MDOT ROAD DESIGN MANUAL OR FACILITY DESIGN GUIDE, STANDARD PLATES AND DETAILS FOR REQUIREMENTS.

SHOW SURFACE DRAINAGE PATTERNS IN THE PLAN VIEW. PROVIDE DIMENSIONS FOR WIDTH AND DEPTH OF THE DRAINAGE SWALE AS WELL AS THE TYPE OF IMPERVIOUS LINER MATERIAL. COLLECT SURFACE WATER RUNOFF ABOVE AND DIVERT AROUND WALL FACE.

DETAIL LINES AND GRADES OF THE INTERNAL DRAINAGE COLLECTION PIPE. DETAIL OR NOTE THE DESTINATION OF INTERNAL WALL DRAINS AS WELL AS THE METHOD OF TERMINATION (DAYLIGHT END OF PIPE OR CONNECTION INTO HYDRAULIC STRUCTURE). SPACE DRAIN PIPE OUTLET NOT MORE THAN 150 FT.

SOFT SOILS AND/OR HIGH WATER CONDITIONS (DEFINED AS GROUNDWATER WITHIN A DEPTH EQUAL TO THE WALL HEIGHT (H) MAY NOT BE SUITABLE FOR APPLICATION OF STANDARD DESIGNS AND REQUIRE SPECIAL CONSIDERATION BY THE FOUNDATIONS UNIT.

STANDARD DESIGN CHARTS ARE NOT APPLICABLE TO:

- PROJECT/SITES WHERE FOUNDATION SOILS SHEAR STRENGTH AND/OR BEARING RESISTANCE DO NOT MEET OR EXCEED VALUES USED IN THE DEVELOPMENT OF STANDARD DESIGN CHARTS.
- PROJECTS WITH A LARGE QUANTITY OF FACE AREA WHERE PROJECT SPECIFIC DESIGNS ARE RECOMMENDED, AS DEFINED IN MNDOT ROAD DESIGN MANUAL OR FACILITY DESIGN GUIDE.
- WHERE SLOPES IN FRONT OF WALL ARE STEEPER THAN 1:3.
- WHERE MAXIMUM WALL HEIGHT EXCEEDS 12 FT.
- WHERE WALLS ARE TIERED.
- WALLS WITH NOISE WALLS.

IF USING CONCRETE RAILING, INCLUDE STANDARD BRIDGE DETAIL "CONCRETE RAILING (TYPE F)"  
IN PLAN SET.

PROVIDE PROJECT SPECIFIC AESTHETIC REQUIREMENTS INCLUDING COLOR AND FASCIA SURFACING IN THE SPECIAL PROVISIONS.

MnDOT ROAD DESIGN MANUAL OR FACILITY DESIGN GUIDE CONTAINS GUIDELINES, TRAFFIC SAFETY AND OTHER ASPECTS.

## LEAD EXPERT OFFICE

**AMBER BLANCHARD**  
ACTING DIRECTOR  
OFFICE OF MATERIALS  
AND ROAD RESEARCH



STANDARD PLAN 5-297.640	1 OF 2
-------------------------	--------

1 OF 2

APPROVED: 03-29-2023  
REVISED:

THOMAS STYRBICKI  
STATE DESIGN ENGINEER

STATE PROJ. NO.

THOMAS STYRBICKI  
STATE DESIGN ENGINEER

STATE PROJ. NO.

**MODULAR BLOCK RETAINING WALL  
GENERAL NOTES**

(T.H. ) SHEET NO. **13** OF **43** SHEETS



MODULAR WALL STORMWATER MANAGEMENT AND VEGETATION ESTABLISHMENT NOTES

THE FOLLOWING MUST BE ADDRESSED IN DESIGN AND INCORPORATED INTO THE PLAN SUBMITTALS:

1. STORMWATER MANAGEMENT OF OVERLAND AND SLOPE TOE FLOWS-  
INCLUDE IN WALL PACKAGE SUBMITTAL THAT DETAILS HOW OVERLAND AND TOE OF SLOPE FLOWS WILL BE MANAGED AROUND AND THROUGH DURING ALL PHASES OF WALL CONSTRUCTION.  
INCLUDE THE FOLLOWING:  
A. DESCRIBE EROSION PREVENTION BMPS, AND METHODS FOR APPROPRIATE INSTALLATION.  
B. DETAIL HOW TEMPORARY OR PERMANENT STABILIZATION WILL BE INCORPORATED INTO THE WORK.  
C. DETAIL HOW SLOPE TOE WILL BE DEFENDED FROM SEDIMENT LOSS DURING ALL PHASES OF WALL CONSTRUCTION, INCLUDING CONTINGENCY PROGRAM FOR SEDIMENT RECOVERY OUTSIDE OF CONSTRUCTION LIMITS.
2. TOP AND END WALL STABILIZATION-  
INCLUDE IN WALL PACKAGE SUBMITTAL ESTIMATED QUANTITIES, PRECISE BEST PRACTICES FOR EXPOSED SOIL STABILIZATION FOR ALL PHASES OF CONSTRUCTION. DETAIL TIME FRAMES FOR INTERIM AND CONCURRENT STABILIZATION MEASURES, ALONG WITH STANDARD INSTALLATION DETAILS THAT FOLLOW MNDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION (LATEST EDITION) OR NATIONWIDE GENERAL INDUSTRY PRACTICE. USE 1:4 SLOPE STEEPNESS TO DIFFERENTIATE BETWEEN RELATIVELY FLAT AND CRITICAL SLOPE STEEPNESS FOR DETERMINING APPROPRIATE SLOPE COVERS THAT PREVENT EROSION DURING THE VEGETATIVE ESTABLISHMENT PHASE. INCLUDE THE FOLLOWING:  
A. DEFINE THE COHESIVE SOIL TYPES FOR MAXIMIZING EROSION STABILITY FOR SWALE AND UPGRADE AREAS.  
B. OBTAIN SOIL FERTILITY TEST RESULTS OF PROPOSED TOPSOILS. BASE FERTILIZER APPLICATION RECOMMENDATION FROM TEST RESULTS.  
C. DEFINE ADDITIONAL SOIL AMENDMENTS TO MAXIMIZE VEGETATIVE GROWTH.  
D. DEFINE THE SEED MIXTURES APPROPRIATE TO SOLAR ASPECT, REGION, ADJACENT PERENNIAL COVER TYPES, AND EXPECTED MAINTENANCE PROTOCOLS.  
E. USE CRITICAL PATH PLANNING FOR OPTIMUM SEEDING DATE INCORPORATION INTO THE WORK..
3. TOE OF WALL STABILIZATION-  
INCLUDE ITEMS ABOVE IN PACKAGE SUBMITTAL FOR EXPOSED SOIL STABILIZATION, WITH ADDITIONAL STABILIZATION PROGRAM DELIVERY IF CONVEYANCE FLOW OR SATURATED SOIL CONDITION IS ALSO PRESENT.
4. DRAIN TILE OUTLETS-  
INCLUDE IN WALL PACKAGE SUBMITTAL IMMEDIATE STABILIZATION PROGRAM INCLUDING BMPS FOR DRAIN TILE OUTLET OR WALL OPENINGS OR PENETRATIONS.
5. CONCRETE WASTE/EXCESS MATERIAL MANAGEMENT-  
INCLUDE IN WALL PACKAGE SUBMITTAL A MATERIAL MANAGEMENT PROGRAM THAT ADDRESSES CONCRETE WASTE GROUND CONTACT PREVENTION, SPILL MANAGEMENT, AND EXCESS MATERIAL DISPOSAL.
6. VEGETATION MANAGEMENT PROGRAM-  
A. PREVENT EROSION. SUBMIT A CONTINGENCY PLAN FOR EXTREME WEATHER GREATER THAN A 2 YEAR TYPE STORM AND EROSION CONDITIONS. IMMEDIATELY IMPLEMENT THE CONTINGENCY PLAN WHEN DAMAGE IS DETECTED.  
B. ESTABLISH VEGETATION. SUBMIT A VEGETATION ESTABLISHMENT MONITORING PROGRAM THAT WEEKLY OR MORE OFTEN DETERMINES PLANT HEALTH AND DEVELOPMENT. DEVELOP A CORRECTIVE ACTION PLAN WHEN VEGETATION IS NOT DEVELOPING ADEQUATE COVER DENSITY OR SPECIES DIVERSITY BASED ON SEED MIX DEFINED IN THE WALL SUBMITTAL.  
C. PROVIDE AUTOMATED TEMPORARY IRRIGATION SYSTEM UNTIL PERENNIAL SEEDS OR SOD COMPONENTS ARE A MINIMUM OF 6 INCHES OF COVER HEIGHT. APPLY WATER AT A RATE OF 1 INCH PER WEEK, EVENLY AND UNIFORMLY APPLIED EACH DAY. IRRIGATION IS NOT NECESSARY ON RAIN DAYS. ENSURE APPROPRIATE SPECIES DENSITY HAS OCCURRED THAT MEETS CONTRACT REQUIREMENTS AND ENVIRONMENTAL COMMITMENTS.  
D. CONTROL ANNUAL WEEDS THAT LIMIT PERENNIAL VEGETATIVE COVER BY MECHANICAL METHODS.  
E. CONTROL ALL NOXIOUS STATE LISTED WEEDS BY MECHANICAL OR PRECISION HERBICIDE METHODS.
7. LIST AND PROVIDE TEMPORARY AND PERMANENT STABILIZATION ESTIMATED QUANTITY ITEMS AND TABULATIONS IN WALL SUBMITTAL PACKAGE. THE TABULATION OF ESTIMATED QUANTITIES SHOULD INCLUDE ITEMS LIKE TOPSOIL BORROW, FERTILIZER TYPES, TEMPORARY EROSION PREVENTION ITEMS, PERMANENT EROSION PREVENTION ITEMS, SEED MIXTURE TYPES, SEDIMENT CONTROL BMP TYPES, AND IRRIGATION.

LEAD EXPERT OFFICE

AMBER BLANCHARD  
ACTING DIRECTOR  
OFFICE OF MATERIALS  
AND ROAD RESEARCH



STANDARD PLAN 5-297.640

2 OF 2

THOMAS STYRBECKI  
STATE DESIGN ENGINEER

APPROVED: 03-29-2023  
REVISED:

STATE PROJ. NO.

MODULAR BLOCK RETAINING WALL  
STORMWATER MANAGEMENT AND VEGETATION NOTES

(T.H. )

SHEET NO. 14 OF 43 SHEETS




MODULAR BLOCK WALL REINFORCEMENT LAYOUT TABLE											
CASE 1 - LEVEL FILL											
MBW REINFORCEMENT CLASS	① MINIMUM REINFORCEMENT LENGTH, L (FT.)	② MAXIMUM WALL HEIGHT, H (FT.)	③ NOMINAL BLOCK WIDTH (IN.)	WALL BATTER (DEGREES)	⑪ MAXIMUM UNREINFORCED WALL HEIGHT, A (IN.)	ZONE 1		ZONE 2		ZONE 3	
						H1 (FT.)	S1max (IN.)	H2 (FT.)	S2max (IN.)	H3 (FT.)	S3max (IN.)
1050	0.8H	12.0	12	0 to 4	12	8	24	4	16	0	0
				4 to 8	12	4	24	4	16	4	8
			18 OR 21	0 to 4	20	5	32	3	24	4	16
				4 to 8	20	5	32	5	24	2	16
1400	0.8H	12.0	12	0 to 4	12	4	32	2	24	6	16
				4 to 8	12	4	24	5	16	3	8
			18 OR 21	0 to 4	20	6	32	5	32	1	24
				4 to 8	20	6	32	5	32	1	24
2100	0.8H	12.0	12	0 to 4	12	8	24	4	16	0	0
				4 to 8	12	6	24	6	16	0	0
			18 OR 21	0 to 4	20	10	32	2	24	0	0
				4 to 8	20	8	32	4	24	0	0

NOTES TO CONTRACTOR:

SEE STANDARD PLAN 5-297.640 FOR STORMWATER MANAGEMENT AND VEGETATION ESTABLISHMENT NOTES.

- ① MINIMUM REINFORCEMENT LENGTH FROM TABLE OR 7 FT. MINIMUM, WHICHEVER IS GREATER AS MEASURED FROM THE FRONT OF THE MODULAR BLOCK UNIT. THE GEOGRID REINFORCEMENT SHALL EXTEND TO THE FRONT BLOCK FACE.
- ② AS MEASURED FROM TOP OF CAP UNIT TO BOTTOM OF LOWERMOST BLOCK UNIT.
- ③ BLOCK WIDTH - MEASURED FROM FRONT TO BACK FACE OF BLOCK UNIT.
- ④ PAY LIMITS OF STRUCTURAL EXCAVATION. ACTUAL EXCAVATION SLOPE IS DETERMINED BY OSHA REGULATIONS AND IN-SITU SOILS; EXCAVATION BEYOND "LIMITS OF STRUCTURAL EXCAVATION" AT CONTRACTOR'S EXPENSE.
- ⑤ THE WRAP BACK LENGTH FOR GEOTEXTILE TYPE 1 SHALL NOT BE MORE THAN 6".
- ⑥ INSPECT EXCAVATION SLOPES FOR ACTIVE SEEPAGE AND PLACE ADDITIONAL DRAINS WHERE SEEPAGE OCCURS. DRAINS SHALL OUTLETSLOPE EVERY 150 FT. MAX.
- ⑦ PLACE DRAIN PIPE WITHIN REINFORCED FILL AT THE INTERFACE OF THE RETAINED BACKFILL AND THE FOUNDATION SOIL AND RUN ENTIRE LENGTH OF WALL. OUTLET THROUGH WALL FACE OR TO STORM SEWER OUTLET AT LEAST EVERY 150 FT. OF WALL. DO NOT OUTLET ONTO A SIDEWALK, ROADWAY OR CURB.
- ⑧ 4" THERMOPLASTIC PERFORATED PIPE, SPEC. 3245, WRAP WITH TYPE 1 GEOTEXTILE, SPEC. 3733 (TYP.). INSTALLATION IN ACCORDANCE WITH SPEC. 2502. USE PERFORATED DRAIN PIPE EXCEPT FOR PIPE EXTENDING THROUGH BLOCK UNIT AND EXTENDING THROUGH FILL OUTSIDE WALL WHICH SHALL BE SOLID PIPE. PLACE RODENT SCREEN ON END OF PIPE. SCREEN SHALL BE FABRICATED FROM CARBON STEEL FLATTENED EXPANDED METAL, STYLE 1/2" NO. 4F. IT SHALL BE HOT DIPPED GALVANIZED AFTER FABRICATION.
- ⑨  $S_{max} = 0.5 S1_{max}$  IF THE WALL HEIGHT IS WITHIN ZONE 1.  
 $S_{max} = 0.5 S2_{max}$  IF THE WALL HEIGHT IS WITHIN ZONE 2.  
 $S_{max} = 0.5 S3_{max}$  IF THE WALL HEIGHT IS WITHIN ZONE 3.  
 $S_{base}$  SHALL BE ONE (1) BLOCK HEIGHT MINIMUM.
- ⑩ IF PIPE AT THIS ELEVATION CANNOT BE SLOPED TO DRAIN, OMIT THE LOWER DRAIN AND USE "OPTIONAL CONCRETE PAD" DETAIL THAT SHOWS DRAIN PIPE ON TOP OF THE LEVELING PAD.
- ⑪ MAXIMUM UNREINFORCED VERTICAL DISTANCE BELOW TOP OF WALL.
- ⑫ ATTACH CAP BLOCK WITH ADHESIVE.




OPTIONAL CONCRETE PAD  
NOT TO SCALE

INSTRUCTIONS TO CONTRACTOR:

USE AS MANY ZONES AS WALL HEIGHT REQUIRES, STARTING WITH ZONE 1 AND ADDING ADDITIONAL ZONES TO THE BOTTOM OF THE WALL AS NEEDED TO MAKE UP THE TOTAL WALL HEIGHT (H) NEEDED.

REINFORCEMENT CLASS, NOMINAL BLOCK WIDTH AND WALL BATTER ARE GENERALLY THE CONTRACTOR'S OPTION TO SELECT FROM MnDOT APPROVED PRODUCTS LISTS POSTED AT <https://www.dot.state.mn.us>



LEAD EXPERT OFFICE

AMBER BLANCHARD  
ACTING DIRECTOR  
OFFICE OF MATERIALS  
AND ROAD RESEARCH



STANDARD PLAN 5-297.641

1 OF 1

THOMAS STYBRICKI  
STATE DESIGN ENGINEER

APPROVED: 03-29-2023  
REVISED:

STATE PROJ. NO.

MODULAR BLOCK RETAINING WALL  
SOIL REINFORCEMENT FOR LEVEL FILL, CASE 1








(T.H. )

SHEET NO. 15 OF 43 SHEETS

NOTES:

CORRECT ORIENTATION OF GEOSYNTHETIC TO OBTAIN PROPER STRENGTH SHALL BE DETAILED ON CONTRACTOR SHOP DRAWINGS.

ADJACENT WIDTHS OF REINFORCEMENT SHALL BE EXTENDED AS NECESSARY AND NOT PLACED DIRECTLY ON TOP OF EACH OTHER.



NOTES:

① USE CAUTION WHEN PLACING CURB WITH GUARDRAIL. CURBS ADVERSELY AFFECT THE PERFORMANCE OF THE GUARDRAIL.

② ALL POSTS MUST BE SLEEVED THROUGH THE GEOGRID.

LEAD EXPERT OFFICE

AMBER BLANCHARD  
ACTING DIRECTOR  
OFFICE OF MATERIALS  
AND ROAD RESEARCH



STANDARD PLAN 5-297.645

1 OF 2

APPROVED: 03-29-2023  
REVISED:



THOMAS STYRICKI  
STATE DESIGN ENGINEER

STATE PROJ. NO.

MODULAR BLOCK RETAINING WALL  
DETAILS



(T.H.)

SHEET NO. 16 OF 43 SHEETS



NOTES:

1. ALL EXPOSED SOIL AREAS MUST BE STABILIZED AS SOON AS POSSIBLE TO LIMIT SOIL EROSION, BUT IN NO CASE LONGER THAN 7 DAYS. IF THERE IS A SCHEDULED PAUSE OF WORK THAT WILL LAST 7 DAYS OR LONGER, ALL SOILS AND STOCKPILES ARE REQUIRED TO BE STABILIZED WITHIN THE FIRST 24 HOURS OF INACTIVITY.
2. THERE SHALL BE NO STOCKPILING INCLUDING TEMPORARY STOCK PILES OF MATERIALS IN WETLAND AREAS.
3. ALL SILT FENCE MUST BE IN PLACE BEFORE ANY LAND IS DISTURBED.
4. ALL REMOVALS TO BE DISPOSED OF LEGALLY.
5. SEE MNDOT STANDARD PLANS FOR MORE RETAINING WALL DETAILS. SHEETS 13 THRU 16.
6. BLOCK AREAS INSTALLED BELOW THE GROUND LEVEL SHALL BE CONSIDERED INCIDENTAL.
7. ACCESS TO JAKE'S AUTO MALL MUST BE OPEN DURING BUSINESS HOURS.



PROPOSED  
RETAINING WALL



800-252-1166 651-454-0002

UTILITIES: CENTURYLINK (763) 712-5017  
CENTERPOINT ENERGY (763) 323-2760  
COMCAST (952) 607-4078  
CONNEXUS ENERGY (763) 323-4268  
XCEL ENERGY (612) 526-4508

DATE REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.  
*Dave Hough*  
DATE 05/29/25 REG. NO. 48768

**RFC ENGINEERING, INC.**  
Consulting Engineers


13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
RETAINING WALL DETAIL




DESIGN BY: LDZ DRAWN BY: LDZ CHECKED BY: DAK

DWG: 2111 RET WALL 1  
DATE: 05/29/25  
JOB NUMBER: 2111  
SHEET: 17 OF 43  
FILE: 33-2-117


# JAKE'S AUTO SOUTH DRIVEWAY STA 20+50




# JAKE'S AUTO NORTH DRIVEWAY STA 23+50



PROPOSED BITUMINOUS DRIVEWAY



PROPOSED CONCRETE




## BALTIMORE STREET AND 171ST AVENUE

### NOTES:

- ALL EXPOSED SOIL AREAS MUST BE STABILIZED AS SOON AS POSSIBLE TO LIMIT SOIL EROSION, BUT IN NO CASE LONGER THAN 7 DAYS. IF THERE IS A SCHEDULED PAUSE OF WORK THAT WILL LAST 7 DAYS OR LONGER, ALL SOILS AND STOCKPILES ARE REQUIRED TO BE STABILIZED WITHIN THE FIRST 24 HOURS OF INACTIVITY.
- ALL REMOVALS TO BE DISPOSED OF LEGALLY.
- SEE DETAIL COMMERCIAL DRIVEWAY RFC-370A1 FOR DRIVEWAY DETAILS.



### ALL DETAILS



800-252-1166 651-454-0002

UTILITIES: CENTURYLINK (763) 712-5017  
CENTERPOINT ENERGY (763) 323-2760  
COMCAST (952) 607-4078  
CONNEXUS ENERGY (763) 323-4268  
XCEL ENERGY (612) 526-4508

### DATE REVISION HISTORY


I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

*Dave Krueger*  
DATE 05/29/25 REG. NO. 48768

**RFC ENGINEERING, INC.**  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

DESIGN BY: LDZ

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
INTERSECTION DETAILS

DRAWN BY: LDZ

CHECKED BY: DAK



DWG: 2111 INT

DATE: 05/29/25

JOB NUMBER: 2111


SHEET: 18 OF 43

FILE: 33-2-118










NOTES:

1. ALL EXPOSED SOIL AREAS MUST BE STABILIZED AS SOON AS POSSIBLE TO LIMIT SOIL EROSION, BUT IN NO CASE LONGER THAN 7 DAYS. IF THERE IS A SCHEDULED PAUSE OF WORK THAT WILL LAST 7 DAYS OR LONGER, ALL SOILS AND STOCKPILES ARE REQUIRED TO BE STABILIZED WITHIN THE FIRST 24 HOURS OF INACTIVITY.
2. ALL LOCATIONS OF STOCKPILES SHALL BE SUBMITTED FOR THE CITY ENGINEERS APPROVAL PRIOR TO STOCKPILING. ALL EROSION CONTROL FOR STOCKPILES SHALL BE PER BMP'S AND SWPPP.
3. ALL SILT FENCE MUST BE IN PLACE BEFORE ANY LAND IS DISTURBED.
4. SEE TREE REMOVAL SHEETS FOR TREE AND PLANT REMOVALS.
5. REFER TO THE FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL THAT NEEDS TO BE PLACED ON TRUNK HIGHWAY 65 WHEN WORKING WITHIN MNDOT ROW.
6. NO LANE CLOSURES ALLOWED FROM 1 PM TO 7 PM ON TRUNK HIGHWAY 65.



WETLAND IMPACT

BITUMINOUS REMOVAL

REMOVE SIGN C-24

SALVAGE SIGN C-22

REMOVE 37 SQ YD OF BITUMINOUS DRIVEWAY

SALVAGE CASTING

REMOVE 70 LF OF CONCRETE CURB

REMOVE 455 SQ YD OF BITUMINOUS

SAWCUT CONCRETE CURB 2 LF STA 9+37.62 SAWCUT AT NEAREST JOINT

TYPE 2 WETLAND FILL 1,130 SQFT

REMOVE 4 LF OF STORM SEWER

SALVAGE SIGN C-23

SAWCUT BITUMINOUS 30 LF STA: 50+67.10

SALVAGE CASTING

REMOVE SIGN C-21

REMOVE 68 LF OF CONCRETE CURB

SAWCUT CONCRETE CURB 2 LF STA 9+37.62 SAWCUT AT NEAREST JOINT

SAWCUT BITUMINOUS 30 LF STA: 9+37.62

DATE 05/29/25 REG. NO. 48768

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.  
*Dave Krueger*  
DATE 05/29/25 REG. NO. 48768


**RFC ENGINEERING, INC.**  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042




S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
REMOVAL PLAN

DWG: 2111 REMOVAL 3  
DATE: 05/29/25  
JOB NUMBER: 2111  
SHEET: 21 OF 43  
FILE: 33-2-121

DESIGN BY: LDZ DRAWN BY: LDZ CHECKED BY: DAK



- NOTES:
1. ALL EXPOSED SOIL AREAS MUST BE STABILIZED AS SOON AS POSSIBLE TO LIMIT SOIL EROSION, BUT IN NO CASE LONGER THAN 7 DAYS. IF THERE IS A SCHEDULED PAUSE OF WORK THAT WILL LAST 7 DAYS OR LONGER, ALL SOILS AND STOCKPILES ARE REQUIRED TO BE STABILIZED WITHIN THE FIRST 24 HOURS OF INACTIVITY.
  2. ALL LOCATIONS OF STOCKPILES SHALL BE SUBMITTED FOR THE CITY ENGINEERS APPROVAL PRIOR TO STOCKPILING. ALL EROSION CONTROL FOR STOCKPILES SHALL BE PER BMP'S AND SWPPP.
  3. ALL SILT FENCE MUST BE IN PLACE BEFORE ANY LAND IS DISTURBED.
  4. SEE TREE REMOVAL SHEETS FOR TREE AND PLANT REMOVALS.
  5. REFER TO THE FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL THAT NEEDS TO BE PLACED ON TRUNK HIGHWAY 65 WHEN WORKING WITHIN MNDOT ROW.
  6. NO LANE CLOSURES ALLOWED FROM 1 PM TO 7 PM ON TRUNK HIGHWAY 65.



800-252-1166 651-454-0002

UTILITIES: CENTURYLINK (763) 712-5017  
CENTERPOINT ENERGY (763) 323-2760  
COMCAST (952) 607-4078  
CONNEXUS ENERGY (763) 323-4268  
XCEL ENERGY (612) 526-4508

DATE REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

DATE 05/29/25 REG. NO. 48768

**RFC ENGINEERING, INC.**  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

DESIGN BY: LDZ

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
REMOVAL PLAN

DRAWN BY: LDZ

CHECKED BY: DAK

DWG: 2111 REMOVAL 4



DATE: 05/29/25

JOB NUMBER: 2111




SHEET: 22 OF 43

FILE: 33-2-122










- NOTES:
1. OBTAIN CITY OF HAM LAKE EROSION CONTROL, GRADING, AND STORMWATER PERMIT. CONTACT CITY OF HAM LAKE 24 HOURS PRIOR TO INSTALLATION OF ANY STORMWATER BMP.
  2. THE GRADING CONTRACTOR IS RESPONSIBLE FOR THE STRIPPING AND STOCKPILING OF TOPSOIL. TOPSOIL SHALL BE STOCKPILED IN AREAS DESIGNATED BY THE ENGINEER.
  3. COVER OR SEED ALL STOCKPILE AREAS WITHIN 24 HOURS OF INACTIVITY.
  4. ALL EXPOSED SOIL AREAS MUST BE STABILIZED AS SOON AS POSSIBLE TO LIMIT SOIL EROSION, BUT IN NO CASE LONGER THAN 7 DAYS. IF THERE IS A SCHEDULED PAUSE OF WORK THAT WILL LAST 7 DAYS OR LONGER, ALL SOILS AND STOCKPILES ARE REQUIRED TO BE STABILIZED WITHIN THE FIRST 24 HOURS OF INACTIVITY. \*SEE SWPPP AND CONSTRUCTION GRADING PLAN FOR DETAILS.
  5. NO CONSTRUCTION ACTIVITY TO BEGIN PRIOR TO SILT FENCE PLACEMENT.
  6. AREAS USING SEDIMENT LOGS WILL BE PLACED AS THE SECOND LAYER OF PERIMETER CONTROL BEHIND THE SILT FENCE, CLOSEST TO THE PROTECTION AREA.
  7. SILT FENCE CANNOT BE REMOVED UNTIL CCWD HAS DETERMINED ALL DISTURBED AREAS ARE FULLY STABILIZED. EROSION CONTROL BLANKET CANNOT BE REMOVED.
  8. ALL GRADING OPERATIONS SHALL BE CONDUCTED IN A MANNER TO MINIMIZE THE POTENTIAL FOR SITE EROSION.
  9. SEDIMENT TRACKED ONTO THE STREET FROM CONSTRUCTION ACTIVITIES WILL BE REMOVED ON A DAILY BASIS.
  10. WHEREVER CONSTRUCTION VEHICLE ACCESS ROUTES INTERSECT PAVED PUBLIC ROADS, PROVISIONS MUST BE MADE TO MINIMIZE THE TRANSPORT OF SEDIMENT(MUD) BY RUNOFF OR VEHICLE TRACKING ONTO THE PAVED ROAD SURFACE. THE ROADS SHALL BE CLEANED THOROUGHLY AT THE END OF EACH DAY. SEDIMENT SHALL BE REMOVED FROM ROADS BY SHOVELING OR SWEEPING AND BE TRANSPORTED TO A SEDIMENT CONTROLLED DISPOSAL AREA. STREET WASHING SHALL BE ALLOWED ONLY AFTER SEDIMENT IS REMOVED IN THIS MANNER.
  11. THE GRADING CONTRACTOR SHALL PROVIDE ALL EROSION CONTROL MEASURES CALLED FOR ON THE PLANS, WHICH MAY INCLUDE SILT FENCE AND ROCK CONSTRUCTION EXITS, WHICH SHALL BE CONSTRUCTED AND MADE SERVICEABLE PRIOR TO COMMENCING ANY GRADING OPERATIONS.
  12. ALL EROSION FACILITIES SHALL BE MAINTAINED BY THE CONTRACTOR DURING GRADING OPERATIONS AND UNTIL AFTER TURF IS ESTABLISHED.
  13. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DISPOSE OF LEGALLY AND OFF-SITE, ALL TREES, STUMPS, BRUSH OR OTHER DEBRIS FROM REMOVALS OR ANY DEBRIS THAT EXISTS WITHIN THE CONSTRUCTION AREAS.
  14. ALL GRADED SLOPES SHALL NOT EXCEED 1:4 EXCEPT FOR SEDIMENTATION PONDS.
  15. THE CONTRACTOR SHALL VERIFY LOCATION AND ELEVATIONS OF ALL UNDERGROUND UTILITIES AND CONNECTION POINTS AND ELEVATIONS PRIOR TO CONSTRUCTION, WITH RESPECTIVE UTILITY COMPANIES, CITY, STATE AND COUNTIES.
  16. PIPE OUTLETS MUST BE PROVIDED WITH ENERGY DISSIPATION WITHIN 24 HOURS OF CONNECTION TO SURFACE WATER.
  17. ALL RIPRAP SHALL BE INSTALLED WITH A FILTER MATERIAL OR SOIL SEPARATION FABRIC AND COMPLY WITH THE 2020 MINNESOTA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS.
  18. TREE PROTECTION CONSISTING OF SNOW FENCE OR SAFETY FENCE INSTALLED AT THE DRIP LINE SHALL BE IN PLACE PRIOR TO THE BEGINNING OF ANY GRADING OR DEMOLITION WORK AT THE SITE.
  19. GRADES SHOWN IN PAVED AREAS REPRESENT FINISH ELEVATION.
  20. ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH STATE AND LOCAL STANDARD SPECIFICATIONS FOR CONSTRUCTION.
  21. SPECIFICATIONS THAT APPLY ARE THE CITY OF HAM LAKE, ANOKA COUNTY, MNDOT AND COON CREEK WATERSHED DISTRICT UNLESS OTHERWISE NOTED.
  22. THE CONTRACTOR SHALL PROVIDE ALL DUST CONTROL. THE COST SHALL BE INCIDENTAL TO THE PROJECT..
  23. PROPOSED CURB AND GUTTER AND BITUMINOUS ROADWAY SHALL MATCH THE EXISTING CURB, GUTTER AND BITUMINOUS.
  24. NOTIFY CITY OF HAM LAKE ENGINEERING DEPT. AT LEAST 24 HOURS PRIOR TO THE CONSTRUCTION OF STORMWATER BMPs.
  25. REFER TO THE FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL THAT NEEDS TO BE PLACED ON TRUNK HIGHWAY 65 WHEN WORKING WITHIN MNDOT ROW.
  26. DEWATERING IS NOT ANTICIPATED DUE TO GROUNDWATER ELEVATION, IF DEWATERING DOES OCCUR IT MUST BE APPROVED BY THE WATERSHED AND CITY OF HAM LAKE.
- DEWATERING AND DRAINING NOTES:
- CONTRACTOR SHALL USE SKIMMERS AND FILTERS PER MANUFACTURERS RECOMMENDED PROCEDURES.
  - DEWATERING SHALL TAKE PLACE AFTER SEDIMENT HAS SETTLED.
  - CONTRACTOR SHALL PREVENT EROSION AND SCOUR AT DISCHARGE POINTS THROUGH THE USE OF AN ENERGY DISSIPATION DEVICE.
  - DEWATERING MUST AVOID NUISANCE CONDITIONS.



## POND 2



## POND 3 AND 4

 800-252-1166 651-454-0002	UTILITIES:	CENTURYLINK (763) 712-5017 CENTERPOINT ENERGY (763) 323-2760 COMCAST (952) 607-4078 CONNEXUS ENERGY (763) 323-4268 XCEL ENERGY (612) 526-4508	DATE	REVISION HISTORY	I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA. <i>Dave Krueger</i> DATE 05/29/25 REG. NO. 48768	<b>RFC ENGINEERING, INC.</b> Consulting Engineers	13635 Johnson Street Ham Lake, MN 55304 Telephone 763-862-8000 Fax 763-862-8042	S.A.P. 197-119-003 S.P. 0208-170 (TH 65) HAM LAKE IMPROVEMENT PROJECT 2111 TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM 64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD GRADING AND DRAINAGE PLAN PONDS	DWG: 2111 GRADING 1
	DATE: 05/29/25	JOB NUMBER: 2111	SHEET: 25 OF 43	FILE: 33-2-125					
DESIGN BY: LDZ		DRAWN BY: LDZ		CHECKED BY: DAK					

NOTES:


1. OBTAIN CITY OF HAM LAKE EROSION CONTROL, GRADING, AND STORMWATER PERMIT. CONTACT CITY OF HAM LAKE 24 HOURS PRIOR TO INSTALLATION OF ANY STORMWATER BMP.
2. THE GRADING CONTRACTOR IS RESPONSIBLE FOR THE STRIPPING AND STOCKPILING OF TOPSOIL. TOPSOIL SHALL BE STOCKPILED IN AREAS DESIGNATED BY THE ENGINEER.
3. COVER OR SEED ALL STOCKPILE AREAS WITHIN 24 HOURS OF INACTIVITY.
4. ALL EXPOSED SOIL AREAS MUST BE STABILIZED AS SOON AS POSSIBLE TO LIMIT SOIL EROSION, BUT IN NO CASE LONGER THAN 7 DAYS. IF THERE IS A SCHEDULED PAUSE OF WORK THAT WILL LAST 7 DAYS OR LONGER, ALL SOILS AND STOCKPILES ARE REQUIRED TO BE STABILIZED WITHIN THE FIRST 24 HOURS OF INACTIVITY. \*SEE SWPPP AND CONSTRUCTION GRADING PLAN FOR DETAILS.
5. NO CONSTRUCTION ACTIVITY TO BEGIN PRIOR TO SILT FENCE PLACEMENT.
6. AREAS USING SEDIMENT LOGS WILL BE PLACED AS THE SECOND LAYER OF PERIMETER CONTROL BEHIND THE SILT FENCE, CLOSEST TO THE PROTECTION AREA.
7. SILT FENCE CANNOT BE REMOVED UNTIL CCWD HAS DETERMINED ALL DISTURBED AREAS ARE FULLY STABILIZED. EROSION CONTROL BLANKET CANNOT BE REMOVED.
8. ALL GRADING OPERATIONS SHALL BE CONDUCTED IN A MANNER TO MINIMIZE THE POTENTIAL FOR SITE EROSION.
9. SEDIMENT TRACKED ONTO THE STREET FROM CONSTRUCTION ACTIVITIES WILL BE REMOVED ON A DAILY BASIS.
10. WHEREVER CONSTRUCTION VEHICLE ACCESS ROUTES INTERSECT PAVED PUBLIC ROADS, PROVISIONS MUST BE MADE TO MINIMIZE THE TRANSPORT OF SEDIMENT(MUD) BY RUNOFF OR VEHICLE TRACKING ONTO THE PAVED ROAD SURFACE, THE ROADS SHALL BE CLEANED THOROUGHLY AT THE END OF EACH DAY. SEDIMENT SHALL BE REMOVED FROM ROADS BY SHOVELING OR SWEEPING AND BE TRANSPORTED TO A SEDIMENT CONTROLLED DISPOSAL AREA. STREET WASHING SHALL BE ALLOWED ONLY AFTER SEDIMENT IS REMOVED IN THIS MANNER.
11. THE GRADING CONTRACTOR SHALL PROVIDE ALL EROSION CONTROL MEASURES CALLED FOR ON THE PLANS, WHICH MAY INCLUDE SILT FENCE AND ROCK CONSTRUCTION EXITS, WHICH SHALL BE CONSTRUCTED AND MADE SERVICEABLE PRIOR TO COMMENCING ANY GRADING OPERATIONS.
12. ALL EROSION FACILITIES SHALL BE MAINTAINED BY THE CONTRACTOR DURING GRADING OPERATIONS AND UNTIL AFTER TURF IS ESTABLISHED.
13. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DISPOSE OF LEGALLY AND OFF-SITE, ALL TREES, STUMPS, BRUSH OR OTHER DEBRIS FROM REMOVALS OR ANY DEBRIS THAT EXISTS WITHIN THE CONSTRUCTION AREAS.
14. ALL GRADED SLOPES SHALL NOT EXCEED 1:4 EXCEPT FOR SEDIMENTATION PONDS.
15. THE CONTRACTOR SHALL VERIFY LOCATION AND ELEVATIONS OF ALL UNDERGROUND UTILITIES AND CONNECTION POINTS AND ELEVATIONS PRIOR TO CONSTRUCTION, WITH RESPECTIVE UTILITY COMPANIES, CITY, STATE AND COUNTIES.
16. PIPE OUTLETS MUST BE PROVIDED WITH ENERGY DISSIPATION WITHIN 24 HOURS OF CONNECTION TO SURFACE WATER.
17. ALL RIPRAP SHALL BE INSTALLED WITH A FILTER MATERIAL OR SOIL SEPARATION FABRIC AND COMPLY WITH THE 2020 MINNESOTA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS.
18. TREE PROTECTION CONSISTING OF SNOW FENCE OR SAFETY FENCE INSTALLED AT THE DRIP LINE SHALL BE IN PLACE PRIOR TO THE BEGINNING OF ANY GRADING OR DEMOLITION WORK AT THE SITE.
19. GRADES SHOWN IN PAVED AREAS REPRESENT FINISH ELEVATION.
20. ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH STATE AND LOCAL STANDARD SPECIFICATIONS FOR CONSTRUCTION.
21. SPECIFICATIONS THAT APPLY ARE THE CITY OF HAM LAKE, ANOKA COUNTY, MNDOT AND COOM CREEK WATERSHED DISTRICT UNLESS OTHERWISE NOTED.
22. THE CONTRACTOR SHALL PROVIDE ALL DUST CONTROL. THE COST SHALL BE INCIDENTAL TO THE PROJECT.
23. PROPOSED CURB AND GUTTER AND BITUMINOUS ROADWAY SHALL MATCH THE EXISTING CURB, GUTTER AND BITUMINOUS.
24. NOTIFY CITY OF HAM LAKE ENGINEERING DEPT. AT LEAST 24 HOURS PRIOR TO THE CONSTRUCTION OF STORMWATER BMPs.
25. REFER TO THE FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL THAT NEEDS TO BE PLACED ON TRUNK HIGHWAY 65 WHEN WORKING WITHIN MNDOT ROW.
26. DEWATERING IS NOT ANTICIPATED DUE TO GROUNDWATER ELEVATION, IF DEWATERING DOES OCCUR IT MUST BE APPROVED BY THE WATERSHED AND CITY OF HAM LAKE.

- DEWATERING AND DRAINING NOTES:
- CONTRACTOR SHALL USE SKIMMERS AND FILTERS PER MANUFACTURERS RECOMMENDED PROCEDURES.
  - DEWATERING SHALL TAKE PLACE AFTER SEDIMENT HAS SETTLED.
  - CONTRACTOR SHALL PREVENT EROSION AND SCOUR AT DISCHARGE POINTS THROUGH THE USE OF AN ENERGY DISSIPATION DEVICE.
  - DEWATERING MUST AVOID NUISANCE CONDITIONS.



STOCKPILE & LOW PONT GRADING STA 10+00 TO 14+00

MNDOT DITCH ALONG TRUNK HIGHWAY 65



LOW PONT GRADING STA 27+00 TO 30+00



800-252-1166 651-454-0002

UTILITIES: CENTURYLINK (763) 712-5017  
CENTERPOINT ENERGY (763) 323-2760  
COMCAST (952) 607-4078  
CONNEXUS ENERGY (763) 323-4268  
XCEL ENERGY (612) 526-4508

DATE REVISION HISTORY

DATE	REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.  
*Dave Krueger*  
DATE 05/29/25 REG. NO. 48768

**RFC ENGINEERING, INC.**  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042


DESIGN BY: LDZ

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
GRADING AND DRAINAGE PLAN  
MNDOT DITCH AND LOW PONTS








DRAWN BY: LDZ

CHECKED BY: DAK

DWG: 2111 GRADING 2  
DATE: 05/29/25  
JOB NUMBER: 2111  
SHEET: 26 OF 43  
FILE: 33-2-126





- NOTES:
1. ALL EXPOSED SOIL AREAS MUST BE STABILIZED AS SOON AS POSSIBLE TO LIMIT SOIL EROSION, BUT IN NO CASE LONGER THAN 7 DAYS. IF THERE IS A SCHEDULED PAUSE OF WORK THAT WILL LAST 7 DAYS OR LONGER, ALL SOILS AND STOCKPILES ARE REQUIRED TO BE STABILIZED WITHIN THE FIRST 24 HOURS OF INACTIVITY.
  2. THERE SHALL BE NO STOCKPILING INCLUDING TEMPORARY STOCK PILES OF MATERIALS IN WETLAND AREAS.
  3. COVER OR SEED ALL STOCKPILE AREAS WITHIN 24 HOURS OF INACTIVITY.
  4. ALL SILT FENCE MUST BE IN PLACE BEFORE ANY LAND IS DISTURBED.
  5. ALL REMOVALS TO BE DISPOSED OF LEGALLY.
  6. \* PIPE LENGTH INCLUDES APRON.
  7. \*\* NEENAH FOUNDRY R-3067; EAST JORDAN IRON WORKS V-7030; D&L FOUNDRY I-1804.
  8. \*\* NEENAH FOUNDRY R-1733; EAST JORDAN IRON WORKS V-1280; D&L FOUNDRY A-1028.



STORM DRAIN

STRUCTURE	STATION	LOCATION	SIZE OF STRUCTURE	DESIGN	TOP OF CASTING OR INLET	INVERT	CASTING ASSEMBLY (NEENAH, EJ, DL)**	TYPE GRATE (NEENAH CASTINGS)	12"	15"	18"	24"	36"	30"	36"	PIPE APRON	TRASH GUARD	APRON	FLOWS TO	INLET	% GRADE
									R.C.P. LIN FT	R.C.P. LIN FT	R.C.P. LIN FT	R.C.P. LIN FT	R.C.P. LIN FT	R.C.P. LIN FT	R.C.P. LIN FT						
FES 33	12+03.6	RT.		FES		909.40															
CBMH 32	10+22	RT.	48" Ø	RFC-465A1	913.37	910.37	R-3067	L			6					6.1	1	1	CBMH 31	909.30	0.80
CBMH 31	12+03.5	RT.	48" Ø	RFC-465C	912.39	909.15	R-1733	-		181									CBMH 31	909.40	0.53
CBMH 30	14+00.1	RT.	48" Ø	RFC-465C	912.16	906.74	R-1733	-					62						CBMH 30	906.74	1.20
FES 29	12+49.9	LT.		FES		909.25													CBMH 30	906.74	1.20
CB 28	13+08.2	RT.	2' x 3'	RFC-459B	911.05	907.93	R-3067	c											CBMH 30	906.74	1.20
CBMH 27	13+08.2	LT.	48" Ø	RFC-465A1	911.05	906.84	R-3067	c	31										CBMH 27	907.38	3.09
STUB 26	14+57.5	LT.		FES	907.8	907.80		-											CBMH 27	907.50	1.39
CBMH 25	14+57.5	LT.	60" Ø	RFC-465A1	911.84	906.30	R-3067	L											CBMH 25	906.30	0.38
CBMH 24	14+57.5	RT.	84" Ø	RFC-465A1	911.84	906.10	R-3067	L											CBMH 25	907.64	1.67
STUB 23	16+62.9	LT.		FES	905.9	905.90		-											CBMH 24	906.10	0.65
CBMH 22	16+62.9	LT.	48" Ø	RFC-465A1	912.20	905.80	R-3067	L											CBMH 24	906.10	0.65
CBMH 21	16+62.9	RT.	96" Ø	RFC-465A3	912.20	905.47	R-3067	L											CBMH 21	905.47	0.30
FES 101	POND 1			FES		905.30													CBMH 21	905.47	0.30
																			CBMH 22	905.80	1.04
																			CBMH 21	905.47	1.07
																			FES 20	905.30	0.41
																			FES 100	905.20	0.22
TOTALS									31	181	312	236	209	38	36	25.7	5	5			



UTILITIES: CENTURYLINK (763) 712-5017  
CENTERPOINT ENERGY (763) 323-2760  
COMCAST (952) 607-4078  
CONNEXUS ENERGY (763) 323-4268  
XCEL ENERGY (612) 526-4508

DATE	REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.  
*David Houghton*  
DATE 05/29/25 REG. NO. 48768


**RFC ENGINEERING, INC.**  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
STORM DETAILS  
BALTIMORE STREET




DWG: 2111 STORM 1  
DATE: 05/29/25  
JOB NUMBER: 2111  
SHEET: 27 OF 43  
FILE: 33-2-127

DESIGN BY: LDZ DRAWN BY: LDZ CHECKED BY: DAK







NOTES:

1. ALL EXPOSED SOIL AREAS MUST BE STABILIZED AS SOON AS POSSIBLE TO LIMIT SOIL EROSION, BUT IN NO CASE LONGER THAN 7 DAYS. IF THERE IS A SCHEDULED PAUSE OF WORK THAT WILL LAST 7 DAYS OR LONGER, ALL SOILS AND STOCKPILES ARE REQUIRED TO BE STABILIZED WITHIN THE FIRST 24 HOURS OF INACTIVITY.
2. THERE SHALL BE NO STOCKPILING INCLUDING TEMPORARY STOCK PILES OF MATERIALS IN WETLAND AREAS.
3. COVER OR SEED ALL STOCKPILE AREAS WITHIN 24 HOURS OF INACTIVITY.
4. ALL SILT FENCE MUST BE IN PLACE BEFORE ANY LAND IS DISTURBED.
5. ALL REMOVALS TO BE DISPOSED OF LEGALLY.
6. \* PIPE LENGTH INCLUDES APRON.
7. \*\* NEENAH FOUNDRY R-3067; EAST JORDAN IRON WORKS V-7030; D&L FOUNDRY I-1804.
8. \*\* NEENAH FOUNDRY R-1733; EAST JORDAN IRON WORKS V-1280; D&L FOUNDRY A-1028.



STORM DRAIN																			
STRUCTURE	STATION	LOCATION	SIZE OF STRUCTURE	DESIGN	TOP OF CASTING OR INLET	INVERT	CASTING ASSEMBLY (NEENAH, EJ, DL)**	TYPE GRATE (NEENAH CASTINGS)	12"	15"	18"	15"	18"	PIPE	TRASH	APRON	FLOWS TO	INLET	% GRADE
									R.C.P. LIN FT	R.C.P. LIN FT	R.C.P. LIN FT	C.P.P. LIN FT	C.P.P. LIN FT	APRON LIN FT	GUARD EACH	EACH EACH			
STUB 6	22+55.8	RT.		FES		905.87													
										38							CBMH 4	905.68	0.50
CB 5	22+81.4	LT.	2' x 3'	RFC-459B	908.99	905.85	R-3067	L											
									33								CBMH 4	905.68	0.51
CBMH 4	22+93.6	RT.	48" ø	RFC-465A1	909.06	905.68	R-3067	L											
										97							CBMH 2	905.19	0.51
CB 3	23+90.2	LT.	2' x 3'	RFC-459B	909.66	906.55	R-3067	L											
									31								CBMH 2	906.35	0.65
CBMH 2	23+91.7	RT.	60" ø	RFC-465A3	909.66	905.19	R-3067	L											
													35	2.6	1	1	FES 1	905.00	0.50
FES 11	25+27.5	RT.		FES		905.00													
											71			12.2	2	2	FES 10	905.00	0.00
CB 35	18+03.8	LT.	2' x 3'	RFC-459B	911.10	908.00	R-3067	L											
									31								CBMH 34	907.80	0.65
CBMH 34	18+03.8	RT.	48" ø	RFC-465A1	911.10	907.70	R-3067	L											
										141							CBMH 21	906.00	1.21
STUB 73	19+41.1	RT.		FES		906.65													
										9							CBMH 72	906.59	0.69
CBMH 72	19+40.7	RT.	48" ø	RFC-465A1	910.04	906.22	R-3067	L											
											76						CBMH 71	905.84	0.50
CBMH 71	20+10.5	LT.	96" ø	RFC-465A3	909.49	905.84	R-3067	L											
													16	2.6	1	1	FES 70	905.73	0.60
CB 82	21+70.9	RT.	2' x 3'	RFC-459B	908.44	905.06	R-3067	c											
										31							CBMH 81	904.90	0.52
CBMH 81	21+70.9	LT.	72" ø	RFC-465A3	908.44	904.90	R-3067	c											
												16		2.2	1	1	FES 80	904.80	0.56
TOTALS									95	316	147	16	51	19.6	5	5			



UTILITIES: CENTURYLINK (763) 712-5017  
CENTERPOINT ENERGY (763) 323-2760  
COMCAST (952) 607-4078  
CONNEXUS ENERGY (763) 323-4268  
XCEL ENERGY (612) 526-4508

DATE	REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.  
*David R. Ruppel*  
DATE 05/29/25 REG. NO. 48768



**RFC ENGINEERING, INC.**  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

DESIGN BY: LDZ

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
STORM DETAILS  
173RD LANE & BALTIMORE STREET  
CHECKED BY: DAK

DWG: 2111 STORM 2  
DATE: 05/29/25  
JOB NUMBER: 2111  
SHEET: 28 OF 43  
FILE: 33-2-128










STORM DRAIN

STRUCTURE	STATION	LOCATION	SIZE OF STRUCTURE	DESIGN	TOP OF CASTING OR INLET	INVERT	CASTING ASSEMBLY (NEENAH, E.J., DL)**	TYPE GRATE (NEENAH CASTINGS)	18" R.C.P. LIN FT	24" R.C.P. LIN FT	24" C.P.P. LIN FT	PIPE APRON LIN FT	TRASH GUARD EACH	APRON EACH	FLOWS TO	INLET	% GRADE
STUB 46	26+73.8	LT.		FES	907.85	907.85											
									10						CBMH 45	907.75	1.04
CBMH 45	26+73.8	LT.	48" Ø	RFC-465A1	911.36	907.75	R-3067	L									
									31						CBMH 44	907.40	1.14
CBMH 44	26+73.8	RT.	48" Ø	RFC-465A1	911.36	907.40	R-3067	L									
										300					CBMH 41	905.90	0.50
STUB 43	29+72.5	LT.		FES	906.35	906.35											
									10						CBMH 42	906.25	1.04
CBMH 42	29+72.9	LT.	48" Ø	RFC-465A1	910.78	906.25	R-3067	L									
									31						CBMH 41	905.90	1.13
CBMH 41	29+73.8	RT.	60" Ø	RFC-465A3	910.78	905.90	R-3067	L									
											63	3.4	1	1	FES 40	905.50	0.60
FES 51	30+91.1	RT.		FES		906.80											
									58			12.2	2	2	FES 50	906.00	1.14
FES 63	31+34.6	RT.		FES		905.50											
											30	3.4	1	1	CBMH 62	905.34	0.48
CBMH 62	31+53	RT.	48" Ø	RFC-465A1	909.83	905.34	R-3067	c									
										31					CBMH 61	905.17	0.55
CBMH 61	31+53	LT.	60" Ø	RFC-465A3	909.83	905.17	R-3067	c									
											24	3.4	1	1	FES 60	905.00	0.63
FES 111	POND 4			FES		905.00											
									14			12.2	2	2	FES 110	904.50	1.93
TOTALS									154	331	117	34.6	7	7			

NOTES:

- ALL EXPOSED SOIL AREAS MUST BE STABILIZED AS SOON AS POSSIBLE TO LIMIT SOIL EROSION, BUT IN NO CASE LONGER THAN 7 DAYS. IF THERE IS A SCHEDULED PAUSE OF WORK THAT WILL LAST 7 DAYS OR LONGER, ALL SOILS AND STOCKPILES ARE REQUIRED TO BE STABILIZED WITHIN THE FIRST 24 HOURS OF INACTIVITY.
- THERE SHALL BE NO STOCKPILING INCLUDING TEMPORARY STOCK PILES OF MATERIALS IN WETLAND AREAS.
- COVER OR SEED ALL STOCKPILE AREAS WITHIN 24 HOURS OF INACTIVITY.
- ALL SILT FENCE MUST BE IN PLACE BEFORE ANY LAND IS DISTURBED.
- ALL REMOVALS TO BE DISPOSED OF LEGALLY.
- \* PIPE LENGTH INCLUDES APRON.
- \*\* NEENAH FOUNDRY R-3067; EAST JORDAN IRON WORKS V-7030; D&L FOUNDRY I-1804.
- \*\* NEENAH FOUNDRY R-1733; EAST JORDAN IRON WORKS V-1280; D&L FOUNDRY A-1028.



800-252-1166 651-454-0002

UTILITIES: CENTURYLINK (763) 712-5017  
CENTERPOINT ENERGY (763) 323-2760  
COMCAST (952) 607-4078  
CONNEXUS ENERGY (763) 323-4268  
XCEL ENERGY (612) 526-4508

DATE REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.  
DATE 05/29/25 REG. NO. 48768

RFC ENGINEERING, INC.  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

DESIGN BY: LDZ



S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
STORM DETAILS  
173RD LANE & CHISHOLM STREET  
S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
STORM DETAILS  
173RD LANE & CHISHOLM STREET

DRAWN BY: LDZ

CHECKED BY: DAK

DWG: 2111 STORM 3  
DATE: 05/29/25  
JOB NUMBER: 2111  
SHEET: 29 OF 43  
FILE: 33-2-129







NOTES:

1. ALL EXPOSED SOIL AREAS MUST BE STABILIZED AS SOON AS POSSIBLE TO LIMIT SOIL EROSION, BUT IN NO CASE LONGER THAN 7 DAYS. IF THERE IS A SCHEDULED PAUSE OF WORK THAT WILL LAST 7 DAYS OR LONGER, ALL SOILS AND STOCKPILES ARE REQUIRED TO BE STABILIZED WITHIN THE FIRST 24 HOURS OF INACTIVITY.
2. THERE SHALL BE NO STOCKPILING INCLUDING TEMPORARY STOCK PILES OF MATERIALS IN WETLAND AREAS.
3. COVER OR SEED ALL STOCKPILE AREAS WITHIN 24 HOURS OF INACTIVITY.
4. ALL SILT FENCE MUST BE IN PLACE BEFORE ANY LAND IS DISTURBED.
5. ALL REMOVALS TO BE DISPOSED OF LEGALLY.
6. \*\* NEENAH FOUNDRY R-4990-MX; EAST JORDAN IRON WORKS V-7030; D&L FOUNDRY I-1804.
7. ACCESS TO JAKE'S AUTO MALL MUST REMAIN OPEN DURING BUSINESS HOURS.


TRENCH DRAIN SOUTH JAKE'S AUTO MALL						
STATION	LOCATION	TOP OF CASTING OR INLET	INVERT	CASTING ASSEMBLY (NEENAH, EJ, DL)**	TYPE GRATE (NEENAH CASTINGS)	% GRADE
19+00.00	RT.	908.47	907.50	R-4990-HX	A	2.07
19+41.10	RT.	908.31	906.65	R-4990-HX	A	OUTLET
19+50.00	RT.	908.31	906.71	R-4990-HX	A	0.67
19+96.95	RT.	908.56	907.00	R-4990-HX	A	0.62
20+14.78	RT.	908.56	907.11	R-4990-HX	A	0.62

TRENCH DRAIN DRIVEWAY OF JAKE'S AUTO MALL						
STATION	LOCATION	TOP OF CASTING OR INLET	INVERT	CASTING ASSEMBLY (NEENAH, EJ, DL)**	TYPE GRATE (NEENAH CASTINGS)	% GRADE
19+96.95	RT.	908.82	907.32	R-4990-HX	A	0.67
20+14.78	RT.	908.80	907.20	R-4990-HX	A	OUTLET
20+50.00	RT.	908.21	907.41	R-4990-HX	A	0.61
20+62.59	RT.	908.16	907.49	R-4990-HX	A	0.61

TRENCH DRAIN NORTH JAKE'S AUTO MALL						
STATION	LOCATION	TOP OF CASTING OR INLET	INVERT	CASTING ASSEMBLY (NEENAH, EJ, DL)**	TYPE GRATE (NEENAH CASTINGS)	% GRADE
20+77.06	RT.	907.96	907.26	R-4990-HX	A	0.70
21+00.00	RT.	907.80	907.10	R-4990-HX	A	0.72
21+50.00	RT.	907.76	906.74	R-4990-HX	A	0.72
21+70.73	RT.	907.71	906.59	R-4990-HX	A	0.72
22+00.00	RT.	907.66	906.38	R-4990-HX	A	0.90
22+50.00	RT.	908.16	905.93	R-4990-HX	A	1.06
22+55.80	RT.	908.20	905.87	R-4990-HX	A	OUTLET
22+57.00	RT.	908.27	906.59	R-4990-HX	A	VERTICAL
22+90.49	RT.	908.31	906.91	R-4990-HX	A	0.96
23+00.00	RT.	908.34	907.00	R-4990-HX	A	0.95
23+22.06	RT.	908.49	907.20	R-4990-HX	A	0.91



PROPOSED  
RETAINING WALL



PROPOSED  
TRENCH DRAIN



800-252-1166 651-454-0002

UTILITIES: CENTURYLINK (763) 712-5017  
CENTERPOINT ENERGY (763) 323-2760  
COMCAST (952) 607-4078  
CONNEXUS ENERGY (763) 323-4268  
XCEL ENERGY (612) 526-4508

DATE REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.  
*Dave Kuehn*  
DATE 05/29/25 REG. NO. 48768

**RFC ENGINEERING, INC.**  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

DESIGN BY: LDZ

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
STORM DETAILS  
TRENCH DRAIN

DRAWN BY: LDZ

CHECKED BY: DAK


DWG: 2111 STORM 4  
DATE: 05/29/25  
JOB NUMBER: 2111  
SHEET: 30 OF 43  
FILE: 33-2-130





NOTES:

1. ALL GRADING OPERATIONS SHALL BE CONDUCTED IN A MANNER TO MINIMIZE THE POTENTIAL FOR SITE EROSION.
2. ALL EXPOSED SOIL AREAS MUST BE STABILIZED AS SOON AS POSSIBLE TO LIMIT SOIL EROSION, BUT IN NO CASE LONGER THAN 7 DAYS. IF THERE IS A SCHEDULED PAUSE OF WORK THAT WILL LAST 7 DAYS OR LONGER, ALL SOILS AND STOCKPILES ARE REQUIRED TO BE STABILIZED WITHIN THE FIRST 24 HOURS OF INACTIVITY.
3. SALVAGED TOPSOIL SHALL BE STOCKPILED IN PLACE TO MAINTAIN CONTINUITY OF PROPERTY OWNERS EXISTING TURF CONDITIONS. UPON APPROVAL OF ENGINEER, SOIL MAY BE STOCKPILED UPON REVIEW OF ALTERNATE PLAN PROVIDED BY CONTRACTOR.
4. COVER OR SEED ALL STOCKPILE AREAS WITHIN 24 HOURS OF INACTIVITY.
5. USE SEED MIX 33-261 FOR PONDS AND ALL NON COMMERCIAL TURF ESTABLISHMENT.

CONSTRUCTION EXIT  
SILT FENCE  
RIPRAP, CLASS III WITH FABRIC



SEED MIX 25-131: COMMERCIAL TURF  
MULCH TYPE 1  
PLANT APRIL 1ST - JUNE 1ST FOR SPRING PLANTING OR  
JULY 20TH - SEPTEMBER 20TH FOR FALL PLANTING  
SEED MIX 33-261: PONDS & WET AREAS IN CENTRAL,  
SOUTHERN AND WESTERN MN  
MULCH TYPE 3  
PLANT APRIL 15TH - JULY 20TH FOR SPRING PLANTING OR  
SEPTEMBER 20TH - OCTOBER 20TH FOR FALL PLANTING



800-252-1166 651-454-0002

UTILITIES: CENTURYLINK (763) 712-5017  
CENTERPOINT ENERGY (763) 323-2760  
COMCAST (952) 607-4078  
CONNEXUS ENERGY (763) 323-4268  
XCEL ENERGY (612) 526-4508

DATE	REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS  
PREPARED BY ME OR UNDER MY  
DIRECT SUPERVISION AND THAT I AM A  
DULY REGISTERED PROFESSIONAL  
ENGINEER UNDER THE LAWS OF THE  
STATE OF MINNESOTA.  
*Dave Krueger*  
DATE 05/29/25 REG. NO. 48768

**RFC ENGINEERING, INC.**  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
STORMWATER POLLUTION PREVENTION PLAN

DESIGN BY: LDZ DRAWN BY: LDZ CHECKED BY: DAK

DWG: 2111 SWPPP 1  
DATE: 05/29/25  
JOB NUMBER: 2111  
SHEET: 31 OF 43  
FILE: 33-2-131

NOTES:

1. ALL GRADING OPERATIONS SHALL BE CONDUCTED IN A MANNER TO MINIMIZE THE POTENTIAL FOR SITE EROSION.
2. ALL EXPOSED SOIL AREAS MUST BE STABILIZED AS SOON AS POSSIBLE TO LIMIT SOIL EROSION, BUT IN NO CASE LONGER THAN 7 DAYS. IF THERE IS A SCHEDULED PAUSE OF WORK THAT WILL LAST 7 DAYS OR LONGER, ALL SOILS AND STOCKPILES ARE REQUIRED TO BE STABILIZED WITHIN THE FIRST 24 HOURS OF INACTIVITY.
3. SALVAGED TOPSOIL SHALL BE STOCKPILED IN PLACE TO MAINTAIN CONTINUITY OF PROPERTY OWNERS EXISTING TURF CONDITIONS. UPON APPROVAL OF ENGINEER, SOIL MAY BE STOCKPILED UPON REVIEW OF ALTERNATE PLAN PROVIDED BY CONTRACTOR.
4. COVER OR SEED ALL STOCKPILE AREAS WITHIN 24 HOURS OF INACTIVITY.
5. USE SEED MIX 33-261 FOR PONDS AND ALL NON COMMERCIAL TURF ESTABLISHMENT.

CONSTRUCTION EXIT



SILT FENCE





RIPRAP, CLASS III WITH FABRIC



SEED MIX 25-131: COMMERCIAL TURF  
MULCH TYPE 1  
PLANT APRIL 1ST - JUNE 1ST FOR SPRING PLANTING OR  
JULY 20TH - SEPTEMBER 20TH FOR FALL PLANTING



SEED MIX 33-261: PONDS & WET AREAS IN CENTRAL,  
SOUTHERN AND WESTERN MN  
MULCH TYPE 3  
PLANT APRIL 15TH - JULY 20TH FOR SPRING PLANTING OR  
SEPTEMBER 20TH - OCTOBER 20TH FOR FALL PLANTING



800-252-1166 651-454-0002

UTILITIES: CENTURYLINK (763) 712-5017  
CENTERPOINT ENERGY (763) 323-2760  
COMCAST (952) 607-4078  
CONNEXUS ENERGY (763) 323-4268  
XCEL ENERGY (612) 526-4508

DATE REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS  
PREPARED BY ME OR UNDER MY  
DIRECT SUPERVISION AND THAT I AM A  
DULY REGISTERED PROFESSIONAL  
ENGINEER UNDER THE LAWS OF THE  
STATE OF MINNESOTA.

DATE 05/29/25 REG. NO. 48768

**RFC ENGINEERING, INC.**  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
STORMWATER POLLUTION PREVENTION PLAN

DESIGN BY: LDZ DRAWN BY: LDZ CHECKED BY: DAK

DWG: 2111 SWPPP 2  
DATE: 05/29/25  
JOB NUMBER: 2111  
SHEET: 32 OF 43  
FILE: 33-2-132



STORMWATER POLLUTION PREVENTION PLAN (SWPPP)

CONSTRUCTION ACTIVITY INFORMATION:

STATE AID PROJECT 197-119-003, HAM LAKE, ANOKA COUNTY, MINNESOTA, 55304, 45.2861° LATITUDE NORTH, 93.2336° LONGITUDE WEST (BY ONLINE TOOL).

TOTAL PROJECT DISTURBED AREA IS 10.81 ACRES.

THIS IS A ROAD CONSTRUCTION PROJECT.

0.27 ACRES OF EXISTING IMPERVIOUS SURFACE.  
9.72 ACRES OF EXISTING PERVIOUS SURFACE.  
1.84 ACRES OF NEW IMPERVIOUS SURFACE.  
0.24 ACRES OF NEW PERVIOUS SURFACE.

DRAINAGE IS TO PONDS AND WETLANDS LOCATED EAST AND WEST OF THE IMPROVEMENTS ON MnDOT, CITY, AND PRIVATE PROPERTY. THE WESTERN WETLANDS DRAIN INTO THE MnDOT DITCH ALONG T.H. 65 AND THE EASTERN WETLANDS DRAIN TO COUNTY DITCH 58-3-1. THERE ARE NO SPECIAL WATER OR IMPAIRED WATER WITHIN ONE MILE DOWNSTREAM OF THE PROJECT.

CONTACT INFORMATION:

OWNER: CITY OF HAM LAKE, OWNER CONTACT: DENISE WEBSTER CITY ADMINISTRATOR, DWEBSTER@HAMLAKEMN.GOV, 763-434-9555, 15544 CENTRAL AVENUE, HAM LAKE, MN, 55304

ALTERNATE OWNER CONTACT: DAVID A KRUGLER, CITY ENGINEER. DKRUGLER@RFCENGINEERING.COM 763-862-8000.  
RFC ENGINEERING INC, 13635 JOHNSON STREET NE, HAM LAKE, MN 55304

CONTRACTOR:

ALTERNATE CONTRACTOR CONTACT:

PARTY RESPONSIBLE FOR OPERATION AND MAINTENANCE OF PERMANENT STORMWATER MANAGEMENT SYSTEM: CITY OF HAM LAKE PUBLIC WORKS, JOHN WITKOWSKI, 763-235-1662, 15544 CENTRAL AVENUE, HAM LAKE, MN, 55304

GENERAL CONSTRUCTION PROJECT INFORMATION:

THE PROJECT CONSISTS OF NEW CONSTRUCTION TO EXTEND BALTIMORE STREET FROM 171ST AVENUE TO CHISHOLM STREET. WORK INCLUDES GRADING, AGGREGATE BASE, PLANT MIXED BITUMINOUS SURFACE, STORM DRAINS, AND CONCRETE CURB AND GUTTER.

THE SOILS ON THE SITE ARE PRIMARILY HYDROLOGIC SOIL GROUP TYPE C WITH NO INFILTRATION CAPACITY. THERE IS NO MUCK IN THE WETLANDS. THE GROUNDWATER IN THIS AREA IS HIGH.

GENERAL SITE INFORMATION:

ALL EROSION CONTROL MEASURES MUST BE PLACED PRIOR TO COMMENCEMENT OF LAND DISTURBING ACTIVITIES AND BE MAINTAINED UNTIL ALL DISTURBED AREAS ON THE SITE HAVE BEEN RESTORED.

CONSTRUCTION EXITS SHALL BE SURFACED WITH CRUSHED ROCK AND DESIGNATED PRIOR TO CONSTRUCTION (REFER TO DETAIL).

TRENCHES FOR STORM DRAIN PIPE AND STRUCTURES ARE TO BE BACKFILLED BY THE END OF THE WORK DAY.

NO STORMWATER MITIGATION MEASURES ARE REQUIRED AS THE RESULT OF AN ENVIRONMENTAL, ARCHAEOLOGICAL, OR OTHER REQUIRED LOCAL, STATE, OR FEDERAL REVIEW OF THE PROJECT.

THE PROJECT IS NOT LOCATED IN A KARST AREA.

THE PROJECT DOES NOT DISCHARGE TO A CALCAREOUS FEN LISTED IN MINN. R. 7050.0180, SUBP. 6B.

THE SITE DOES NOT DISCHARGE TO A WATER THAT IS LISTED AS IMPAIRED FOR PHOSPHORUS, TURBIDITY, DISSOLVED OXYGEN OR BIOTIC IMPAIRMENT.

SELECTION OF A PERMANENT STORMWATER MANAGEMENT SYSTEM:

NEW IMPERVIOUS SURFACE CREATED BY THIS PROJECT IS 1.84 ACRES.

PER COON CREEK WATERSHED DISTRICT, ANOKA CONSERVATION DISTRICT, AND MINNESOTA BOARD OF WATER AND SOIL RESOURCES, THERE IS NO INFILTRATION ON SITE DUE TO THE HIGH GROUND WATER TABLE.

HYDROLOGIC REPORT (DRAINAGE CALCULATIONS) AND DRAINAGE MAPS (WITH DRAINAGE DIVIDES) PREPARED FOR THIS PROJECT ARE AVAILABLE IN THE CITY'S ENGINEERS OFFICE. STORM WATER RUNOFF FROM THE SITE DRAINS INTO PONDS AND WETLANDS AND THEN OVERFLOW TO WETLANDS EAST AND WEST OF THE PROJECT. THE WESTERN WETLANDS DRAIN INTO MnDOT DITCH ALONG T.H 65. THE EASTERN WETLANDS DRAIN TO COUNTY DITCH 58-3-1. THE RUNOFF FROM THE SITE WILL BE CONVEYED VIA NEW ON SITE STORM DRAINS. THE LAST STORM DRAIN STRUCTURE JUST PRIOR TO DISCHARGE WILL BE EQUIPPED WITH A SUMP (GRIT CHAMBERS). GRIT CHAMBERS ARE BEING USED DUE TO THE HIGH GROUND WATER TABLE. THE SUMP (GRIT CHAMBERS) ARE SIZED PER COON CREEK WATERSHED DISTRICT REQUIREMENTS.

EROSION PREVENTION PRACTICES:

THERE ARE NO CONSTRUCTION PHASING, VEGETATIVE BUFFER STRIPS, LONG HORIZONTAL SLOPE GRADING FOR THE PROJECT. THERE ARE UNDISTURBED AREAS WITHIN THE PROJECT LIMITS.

ALL DISTURBED AREAS SHALL BE RESTORED WITH SOD, SEED, WOOD FIBER BLANKET, OR PAVED SURFACE WITHIN SEVEN (7) DAYS OF ROUGH GRADING.

ALL EXPOSED SOIL AREAS MUST HAVE TEMPORARY EROSION PROTECTION OR PERMANENT COVER WITHIN SEVEN (7) DAYS AFTER THE AREA IS NOT ACTIVELY BEING WORKED.

FERTILIZER: MnDOT SPECIFICATION 3881, TYPE 2 SEEDING: MnDOT SEED MIXTURE 25-131 OR 33-261 (FOR PONDS), HYDROMULCH: MnDOT SPECIFICATION 3884 TYPE 1 OR 3 WITH APPLICATION RATE PER MnDOT SPECIFICATION 2575.3H.

PROVIDE EROSION CONTROL FABRIC FOR ALL SLOPES STEEPER THAN 1:3.

THERE ARE NO DRAINAGE DITCHES CONSTRUCTED WITH THIS PROJECT.

SEDIMENT CONTROL PRACTICES:

THERE ARE NO DRAINAGE DITCHES OR SEDIMENT BASINS FOR THIS PROJECT.

THERE ARE NO SLOPES WITH A GRADE OF 1:3 OR STEEPER WITH A SLOPE LENGTH GREATER THAN 75 FEET.

THERE ARE NO DRAINAGE INFILTRATION BASINS FOR THIS PROJECT.

ALL SEDIMENT CONTROL DEVICES ARE TO BE IN PLACE PRIOR TO UPSTREAM LAND DISTURBING ACTIVITIES.

WITHIN 24 HOURS OF CONNECTION TO A SURFACE WATER, PIPE OUTLETS MUST CONTAIN RIPRAP, SEED AND PLACE EROSION CONTROL BLANKETS ON DISTURBED AREAS WITHIN 200 LINEAL FEET OF PIPE OUTLETS INCLUDING THE DOWN SLOPE TO THE PIPE OUTLET, SILT FENCING TO BE PLACED AROUND THE DISTURBED AREA AND SILT FENCE ROUTED ACROSS THE TOP OF THE OUTLET.

WITHIN 24 HOURS OF CONNECTION TO A SURFACE WATER, SEED AND PLACE EROSION CONTROL BLANKETS ON DISTURBED AREAS WITHIN 200 FEET OF PIPE INLET INCLUDING THE DOWN SLOPE TO THE PIPE INLET, SILT FENCING TO BE PLACED AROUND THE DISTURBED AREA, PLACE A SECOND SILT FENCE ROUTED ACROSS THE TOP OF THE INLET AND PLACE INLET PROTECTION. PIPE INLET PROTECTION SHALL BE PER BMPS SUCH AS SILT FENCE OR STRAW BALES STAKED AROUND THE APRON OPENING OR OTHER APPROVED EQUIVALENT.

WITHIN 24 HOURS OF CONNECTION TO A SURFACE WATER, SEED AND PLACE EROSION CONTROL BLANKETS ON DISTURBED AREAS WITHIN 200 FEET OF CATCH BASIN INLET. PLACE INLET PROTECTION IMMEDIATELY AFTER STRUCTURE IS BACKFILLED. CATCH BASIN INLET PROTECTION SHALL BE PER BMPS SUCH AS CLEAR ROCK AROUND STEEL PLATE OVER FABRIC OR OTHER APPROVED EQUIVALENT UNTIL THE CATCH BASIN CASTING IS PLACED. IMMEDIATELY AFTER THE CASTING IS PLACED, PROVIDE CATCH BASIN INLET PROTECTION PER BMPS SUCH AS FILTER BAG INSERT OR OTHER APPROVED EQUIVALENT. NO CAPTURED SEDIMENT SHOULD BE ALLOWED TO DROP INTO THE CATCH BASIN.

PROVIDE SILT FENCE DOWNSTREAM OF STOCKPILE AREAS. STOCKPILES ARE NOT TO BLOCK DRAINAGE CONVEYANCE SYSTEMS.

SEDIMENT TRACKED OFFSITE SHALL BE MINIMIZED AND SWEEPED ON A DAILY BASIS.

TEMPORARY SEDIMENTATION BASINS ARE NOT BEING USED TO REDUCE WETLAND IMPACTS, DUE TO THE HIGH GROUND WATER TABLE AND THE LACK OF RIGHT OF WAY.

DEWATERING AND BASIN DRAINING:

ALL DEWATERING IS TO DISCHARGE TO SEDIMENT SACKS, ROCK WEEPER, BIO ROLL AREA, ETC. TO PREVENT EROSION AND MINIMIZE SEDIMENT DISCHARGING FROM THE SITE. EXCESSIVE SEDIMENT-LADEN WATER WILL NOT BE PERMITTED TO DISCHARGE FROM THE SITE. DEWATERING PRACTICES ARE NOT TO CAUSE DOWNSTREAM NUISANCE CONDITIONS, EROSION, OR NON-PERMITTED WETLAND INUNDATION CAUSING ADVERSE IMPACTS. DISCHARGE FROM DEWATERING WILL BE TO WETLANDS. LARGE VOLUMES OF DEWATERING WILL REQUIRE DISCHARGE INTO SEDIMENT SACKS PRIOR TO DISCHARGING INTO THE WETLANDS.

ADDITIONAL BMPS FOR SPECIAL WATERS AND DISCHARGES TO WETLANDS:

THE PROJECT DOES NOT DISCHARGE INTO OR WITHIN 1 MILE OF SPECIAL WATERS.

THERE ARE NO BUFFER ZONES OR UNDISTURBED AREA ZONES.

THE STORM DRAIN SYSTEM WAS SET UP TO DISTRIBUTE THE STORMWATER RUNOFF INTO THE PROJECT PONDS AND WETLANDS AS CLOSE TO EXISTING CONDITIONS AS POSSIBLE. THIS INCLUDED PROVIDING STORM DRAIN ON BOTH SIDES OF THE STREET IN ORDER TO ACHIEVE THIS. THE DRAINAGE IS PENDING APPROVAL BY COON CREEK WATERSHED DISTRICT.

THERE IS CONVERSION OF WETLANDS INTO STORMWATER PONDS.

INSPECTION AND MAINTENANCE:

THE CONTRACTOR SHALL PLACE A RAIN GAUGE ON THE PROJECT SITE AT A LOCATION APPROVED BY THE ENGINEER. RAINFALL DATA SHALL BE KEPT WITH THE SWPPP RECORDS.

THE CONTRACTOR MUST INSPECT THE CONSTRUCTION SITE ONCE EVERY SEVEN (7) DAYS DURING ACTIVE CONSTRUCTION AND WITHIN 24 HOURS AFTER A RAINFALL EVENT GREATER THAN 0.5 INCHES IN 24 HOURS. INSPECTIONS AND MAINTENANCE TO BE RECORDED IN WRITING. THE SWPPP INSPECTION FOR THE CONSTRUCTION IS TO BE CONDUCTED BY \_\_\_\_\_ OF \_\_\_\_\_.

INSPECTIONS FORMS ARE AVAILABLE AT: [HTTPS://TINYURL.COM/2aRMT4KJ](https://tinyurl.com/2aRMT4KJ)

SELECT THE APPROPRIATE INSPECTION FORM FROM THE LIST.

THE CONTRACTOR WILL BE RESPONSIBLE FOR THE OPERATION AND MAINTENANCE OF TEMPORARY AND PERMANENT WATER QUALITY MANAGEMENT DEVICES, AS WELL AS ALL EROSION AND SEDIMENT CONTROL, FOR THE DURATION OF THE PROJECT.

THE CONTRACTOR WILL INVESTIGATE AND MUST COMPLY WITH THE FOLLOWING:

CONTRACTOR MUST INSPECT ALL EROSION PREVENTION AND SEDIMENT CONTROL BMPS AND POLLUTION PREVENTION MANAGEMENT MEASURES TO ENSURE INTEGRITY AND EFFECTIVENESS. CONTRACTOR MUST REPAIR, REPLACE OR SUPPLEMENT ALL NONFUNCTIONAL BMPS WITH FUNCTIONAL BMPS BY THE END OF THE NEXT BUSINESS DAY AFTER DISCOVERY UNLESS ANOTHER TIME FRAME IS SPECIFIED BELOW. CONTRACTOR MAY TAKE ADDITIONAL TIME IF FIELD CONDITIONS PREVENT ACCESS TO THE AREA.

DURING EACH INSPECTION, CONTRACTOR MUST INSPECT SURFACE WATERS, INCLUDING DRAINAGE DITCHES AND CONVEYANCE SYSTEMS BUT NOT CURB AND GUTTER SYSTEMS, FOR EVIDENCE OF EROSION AND SEDIMENT DEPOSITION. CONTRACTOR MUST REMOVE ALL DELTAS AND SEDIMENT DEPOSITED IN SURFACE WATERS, INCLUDING DRAINAGE WAYS, CATCH BASINS, AND OTHER DRAINAGE SYSTEMS AND RESTABILIZE THE AREAS WHERE SEDIMENT REMOVAL RESULTS IN EXPOSED SOIL. CONTRACTOR MUST COMPLETE REMOVAL AND STABILIZATION WITHIN SEVEN (7) CALENDAR DAYS OF DISCOVERY UNLESS PRECLUDED BY LEGAL, REGULATORY, OR PHYSICAL ACCESS CONSTRAINTS. CONTRACTOR MUST USE ALL REASONABLE EFFORTS TO OBTAIN ACCESS. IF PRECLUDED, REMOVAL AND STABILIZATION MUST TAKE PLACE WITHIN SEVEN (7) DAYS OF OBTAINING ACCESS. CONTRACTOR IS RESPONSIBLE FOR CONTACTING ALL LOCAL, REGIONAL, STATE AND FEDERAL AUTHORITIES AND RECEIVING ANY APPLICABLE PERMITS, PRIOR TO CONDUCTING ANY WORK IN SURFACE WATERS.

CONTRACTOR MUST INSPECT CONSTRUCTION SITE VEHICLE EXIT LOCATIONS, STREETS AND CURB AND GUTTER SYSTEMS WITHIN AND ADJACENT TO THE PROJECT FOR SEDIMENTATION FROM EROSION OR TRACKED SEDIMENT FROM VEHICLES. CONTRACTOR MUST REMOVE SEDIMENT FROM ALL PAVED SURFACES WITHIN ONE (1) CALENDAR DAY OF DISCOVERY OR, IF APPLICABLE, WITHIN A SHORTER TIME TO AVOID A SAFETY HAZARD TO USERS OF PUBLIC STREETS.

REPAIR, REPLACE OR SUPPLEMENT ALL PERIMETER CONTROL DEVICES WHEN THEY BECOME NONFUNCTIONAL OR THE SEDIMENT REACHES 1/2 OF THE HEIGHT OF THE DEVICE.

CONTRACTOR MUST DRAIN TEMPORARY AND PERMANENT SEDIMENTATION BASINS AND REMOVE THE SEDIMENT WHEN THE DEPTH OF SEDIMENT COLLECTED IN THE BASIN REACHES TWO FEET OR 1/2 THE STORAGE VOLUME, WHICHEVER IS LESS, WITHIN 72-HOURS OF DISCOVERY.

POLLUTION PREVENTION MANAGEMENT MEASURES:

THE CONTRACTOR SHALL IMPLEMENT THE FOLLOWING POLLUTION PREVENTION MANAGEMENT MEASURES ON THE SITE:

SOLID WASTE: COLLECT SEDIMENT, ASPHALT AND CONCRETE MILLINGS, FLOATING DEBRIS, PAPER, PLASTIC, FABRIC, CONSTRUCTION AND DEMOLITION DEBRIS, AND OTHER WASTES MUST BE DISPOSED OF PROPERLY OFFSITE AND MUST COMPLY WITH MPCA DISPOSAL REQUIREMENTS.

HAZARDOUS MATERIALS: OIL, GASOLINE, PAINT AND ANY HAZARDOUS SUBSTANCES MUST BE PROPERLY STORED, INCLUDING SECONDARY CONTAINMENT, TO PREVENT SPILLS, LEAKS OR OTHER DISCHARGE. RESTRICTED ACCESS TO STORAGE AREAS MUST BE PROVIDED TO PREVENT VANDALISM. STORAGE AND DISPOSAL OF HAZARDOUS WASTE MUST BE IN COMPLIANCE WITH MPCA REGULATIONS.

EXTERNAL WASHING OF TRUCKS, INCLUDING CONCRETE DELIVERY TRUCKS, AND OTHER CONSTRUCTION VEHICLES MUST BE LIMITED TO A DEFINED AREA OF THE SITE. RUNOFF MUST BE CONTAINED AND WASTE PROPERLY DISPOSED OF. NO ENGINE DEGREASING IS ALLOWED ON SITE. CONCRETE WASHOUT ON SITE MUST BE CONTAINED IN A LEAK-PROOF CONTAINMENT FACILITY OR IMPERMEABLE LINER.

THE CITY IS RESPONSIBLE FOR LONG TERM MAINTENANCE OF THE STORM DRAIN INCLUDING THE SUMPS (GRIT CHAMBERS). THE GRIT CHAMBERS ARE TO BE INSPECTED YEARLY AND CLEANED OUT AS NECESSARY TO MAINTAIN FUNCTION.

THE CONTRACTOR IS RESPONSIBLE FOR MONITORING AIR POLLUTION AND ENSURING IT DOES NOT EXCEED LEVELS SET BY LOCAL, STATE, OR FEDERAL REGULATIONS. THIS INCLUDES DUST CREATED BY WORK BEING PERFORMED ON THE SITE. AIR POLLUTION AND DUST CONTROL CORRECTION ARE CONSIDERED INCIDENTAL TO THE UNIT BID PRICES FOR WHICH WORK IS BEING PERFORMED. ADDITIONAL DUST CONTROL MEASURES MAY BE REQUIRED BY THE ENGINEER.

NO SANITARY AND SEPTIC WASTE IS ON THE SITE.

FINAL STABILIZATION:

THE CONTRACTOR MUST ENSURE FINAL STABILIZATION OF THE SITE. FINAL STABILIZATION IS ACHIEVED WHEN ALL SOIL DISTURBING ACTIVITIES AT THE SITE HAVE BEEN COMPLETED AND ALL SOILS ARE STABILIZED BY A UNIFORM PERENNIAL VEGETATIVE COVER WITH A DENSITY OF 70 PERCENT OF THE PERVIOUS SURFACE AREA, OR OTHER EQUIVALENT MEANS NECESSARY TO PREVENT SOIL FAILURE UNDER EROSION CONDITIONS.

ALL TEMPORARY EROSION PROTECTION, INCLUDING SILT FENCE, ARE TO BE REMOVED AFTER FINAL STABILIZATION OF THE SITE. RECORDS RETENTION:

ALL REQUIREMENTS OF THE NPDES PERMIT AND THIS SWPPP SHALL REMAIN IN EFFECT UNTIL ALL LAND DISTURBING ACTIVITY HAS BEEN COMPLETED, ALL FINAL RESTORATION HAS BEEN COMPLETED AND THE NOTICE OF TERMINATION FORM HAS BEEN SUBMITTED TO THE MINNESOTA POLLUTION CONTROL AGENCY (MPCA).

REFER TO OTHER SHEETS OF THIS PLAN SET FOR DETAILED CONSTRUCTION INFORMATION. EXISTING AND PROPOSED GRADES FOR THE ROADWAY ARE SHOWN ON THE PLAN AND PROFILE SHEETS AND ON THE CROSS SECTION SHEETS.

THE CONTRACTOR SHALL MAINTAIN A COPY OF THE PLANS ONSITE AT ALL TIMES UNTIL THE PROJECT HAS BEEN ACCEPTED BY THE CITY. THE CONTRACTOR SHALL UPDATE THE SWPPP AS NECESSARY TO REFLECT CURRENT CONDITIONS ON THE SITE. CONTRACTOR IS TO PROVIDE THE ENGINEER A COPY OF THE REVISED SWPPP. THE REVISED SWPPP IS TO BE MAINTAINED WITH THE CONSTRUCTION SET OF PLANS.

THE CONSTRUCTION PLANS, INCLUDING THE SWPPP, AND THE SWPPP INSPECTION REPORTS ARE TO BE AVAILABLE TO THE ENGINEER AND TO THE MPCA AND COON CREEK WATERSHED DISTRICT INSPECTORS AT ALL TIMES.

THE CONTRACTOR IS TO PROVIDE THE ENGINEER A COPY OF THE SWPPP INSPECTION REPORTS WITHIN SEVEN (7) DAYS AFTER THE INSPECTION.

THE CONTRACTOR IS TO PROVIDE THE ENGINEER A COPY OF THE REVISED SWPPP WITHIN SEVEN (7) DAYS AFTER THE CONTRACTOR REVISES THE SWPPP.

ALL SWPPP INSPECTIONS AND ALL BMPS SHALL BE PLACED UNDER THE SUPERVISION OF A CONSTRUCTION INSTALLER CERTIFIED BY THE MPCA. THE CONSTRUCTION SITE SHALL BE MANAGED AND MAINTAINED BY A MPCA CERTIFIED CONSTRUCTION SITE MANAGEMENT.

THE CONTRACTOR SHALL PROVIDE THE CITY WITH A COPY OF CONSTRUCTION INSTALLER CERTIFICATION AND CONSTRUCTION SITE MANAGEMENT CERTIFICATION. A COPY OF THE CERTIFICATIONS, INCLUDING SWPPP DESIGNER, SHALL BE KEPT WITH THE SWPPP.

THE SWPPP, THE SWPPP INSPECTIONS REPORTS AND MAINTENANCE RECORDS SHALL BE KEPT FOR 3 YEARS.

DRAINAGE CALCULATIONS AND DRAINAGE MAPS WILL BE KEPT BY THE CITY FOR AT LEAST 3 YEARS.

SEQUENCE OF EROSION CONTROL

1. OBTAIN ALL NECESSARY PERMITS, INCLUDING NPDES GENERAL STORMWATER PERMIT.
2. CLEAR AND GRUB SITE.
3. PLACE ALL PERIMETER SEDIMENT CONTROL DEVICES, TEMPORARY SEDIMENTATION BASINS, SILT FLOTATION CURTAINS, AND ROCK CONSTRUCTION EXITS.
4. CONTACT CITY ENGINEER FOR APPROVAL OF SEDIMENT CONTROL DEVICES.
5. ROUGH IN GRADE.
6. PLACE TEMPORARY EROSION CONTROL DEVICES AS NECESSARY.
7. PLACE STORM DRAIN SYSTEM.
8. RE-ADJUST TEMPORARY EROSION CONTROL DEVICES AS NECESSARY. PLACE STORM DRAIN INLET PROTECTION AND OUTLET PROTECTION DEVICES AS NECESSARY.
9. PLACE SITE PAVEMENT.
10. AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, OBTAIN APPROVAL OF CITY ENGINEER.
11. CONTRACTOR TO REMOVE ALL TEMPORARY EROSION CONTROL DEVICES AFTER ACCEPTANCE BY THE CITY.

TABULATION SUMMARY

ITEM	UNIT	TOTAL
SILT FENCE	L.F.	6,621
FES/PIPE OUTLET PROTECTION	EACH	20
CATCH BASIN INLET PROTECTION	EACH	25
CLASS III RIPRAP W/ FABRIC	C.Y.	85.6
GEOTEXTILE FILTER FABRIC	S.Y.	314.6
HYDROMULCH TYPE 3	ACRE	8.02
TURF ESTABLISHMENT: SEED MIX 25-131	ACRE	5.16
TURF ESTABLISHMENT: SEED MIX 33-261	ACRE	2.86



800-252-1166 651-454-0002  
PLOT DATE: 5/29/2025 16:48

UTILITIES: CENTURYLINK (763) 712-5017  
CENTERPOINT ENERGY (763) 323-2760  
COMCAST (952) 607-4078  
CONNEXUS ENERGY (763) 323-4268  
XCEL ENERGY (612) 526-4508

DATE REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

DATE 05/29/25 REG. NO. 48768

RFC ENGINEERING, INC.  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
STORMWATER POLLUTION PREVENTION PLAN

DESIGN BY: LDZ

DRAWN BY: LDZ

CHECKED BY: DAK

DWG: 2111 SWPPP 3


DATE: 05/29/25

JOB NUMBER: 2111

SHEET: 33 OF 43

FILE: 33-2-133

NOTE:  
1. LOCATION OF SIGNS PER MnMUTCD SPECIFICATIONS.  
2. REFER TO THE FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL  
THAT NEEDS TO BE PLACED ON TRUNK HIGHWAY 65 WHEN WORKING  
WITHIN MNDOT ROW.



800-252-1166 651-454-0002

UTILITIES: CENTURYLINK (763) 712-5017  
CENTERPOINT ENERGY (763) 323-2760  
COMCAST (952) 607-4078  
CONNEXUS ENERGY (763) 323-4268  
XCEL ENERGY (612) 526-4508

DATE	REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS  
PREPARED BY ME OR UNDER MY  
DIRECT SUPERVISION AND THAT I AM A  
DULY REGISTERED PROFESSIONAL  
ENGINEER UNDER THE LAWS OF THE  
STATE OF MINNESOTA.  
*Dave Krueger*  
DATE 05/29/25 REG. NO. 48768

**RFC ENGINEERING, INC.**  
Consulting Engineers




13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
SIGNING AND STRIPING PLAN

DESIGN BY: LDZ DRAWN BY: LDZ CHECKED BY: DAK

DWG: 2111 SIGN 1  
DATE: 05/29/25  
JOB NUMBER: 2111  
SHEET: 34 OF 43  
FILE: 33-2-134

- NOTE:
1. LOCATION OF SIGNS PER MnMUTCD SPECIFICATIONS.
  2. REFER TO THE FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL THAT NEEDS TO BE PLACED ON TRUNK HIGHWAY 65 WHEN WORKING WITHIN MNDOT ROW.



800-252-1166 651-454-0002

UTILITIES:

CENTURYLINK	(763) 712-5017
CENTERPOINT ENERGY	(763) 323-2760
COMCAST	(952) 607-4078
CONNEXUS ENERGY	(763) 323-4268
XCEL ENERGY	(612) 526-4508

DATE	REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

*Dave Krueger*

DATE 05/29/25 REG. NO. 48768


**RFC ENGINEERING, INC.**  
Consulting Engineers

13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042


DESIGN BY: LDZ DRAWN BY: LDZ CHECKED BY: DAK


S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
SIGNING AND STRIPING PLAN

DWG: 2111 SIGN 2  
DATE: 05/29/25  
JOB NUMBER: 2111  
SHEET: 35 OF 43  
FILE: 33-2-135









800-252-1166 651-454-0002  
PLOT DATE: 5/29/2025 16:48

UTILITIES:

CENTURYLINK	(763) 712-5017
CENTERPOINT ENERGY	(763) 323-2760
COMCAST	(952) 607-4078
CONNEXUS ENERGY	(763) 323-4268
XCEL ENERGY	(612) 526-4508

DATE	REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

*Dave Krueger*

DATE 05/29/25 REG. NO. 48768


**RFC ENGINEERING, INC.**  
Consulting Engineers


13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
CROSS SECTIONS

DESIGN BY: LDZ  
DRAWN BY: LDZ  
CHECKED BY: DAK

DWG: RC002041  
DATE: 05/29/25  
JOB NUMBER: 2111  
SHEET: 37 OF 43  
FILE: 33-2-137





**800-252-1166 651-454-0002**  
PLOT DATE: 5/29/2025 16:48

UTILITIES:

CENTURYLINK	(763) 712-5017
CENTERPOINT ENERGY	(763) 323-2760
COMCAST	(952) 607-4078
CONNEXUS ENERGY	(763) 323-4268
XCEL ENERGY	(612) 526-4508

DATE	REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

*Dave Krueger*  
DATE: 05/29/25 REG. NO. 48768


**RFC ENGINEERING, INC.**  
Consulting Engineers


13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042


S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
CROSS SECTIONS


DWG:	RC003041
DATE:	05/29/25
JOB NUMBER:	2111
SHEET:	38 OF 43
FILE:	33-2-138


DESIGN BY: LDZ DRAWN BY: LDZ CHECKED BY: DAK











**800-252-1166 651-454-0002**  
PLOT DATE: 5/29/2025 16:48

UTILITIES:

CENTURYLINK	(763) 712-5017
CENTERPOINT ENERGY	(763) 323-2760
COMCAST	(952) 607-4078
CONNEXUS ENERGY	(763) 323-4268
XCEL ENERGY	(612) 526-4508

DATE	REVISION HISTORY

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

*Dave Krueger*

DATE: 05/29/25 REG. NO. 48768

**RFC ENGINEERING, INC.**  
Consulting Engineers


13635 Johnson Street  
Ham Lake, MN 55304  
Telephone 763-862-8000  
Fax 763-862-8042

S.A.P. 197-119-003 S.P. 0208-170 (TH 65)  
HAM LAKE IMPROVEMENT PROJECT 2111  
TH 65 EAST FRONTAGE ROAD CONSTRUCTION FROM  
64' SOUTH 171ST AVE TO 334' SOUTH CROSSTOWN BLVD  
CROSS SECTIONS


DWG:	RC007041
DATE:	05/29/25
JOB NUMBER:	2111
SHEET:	42 OF 43
FILE:	33-2-142

DESIGN BY: LDZ DRAWN BY: LDZ CHECKED BY: DAK





- NOTES:
- THIS SHEET IS FOR **MUCK QUANTITY ESTIMATION ONLY**. NOT TO BE USED FOR CONSTRUCTION PURPOSES.
  - SEE NOTE 11 ON SHEET 2 FOR MORE INFORMATION.
  - MUCK ESTIMATION RANGES FROM STA: 24+00 TO STA: 26+00 AND RUNS AT AN ELEVATION OF 900.
  - IF MUCK IS ENCOUNTERED, ALL MUCK SHALL BE DELIVERED TO THE PUBLIC WORKS SHOP.



MUCK EXCAVATION